ADDENDUM NUMBER ONE

To the Drawings and Project Manual

Dated: 13 May 2025

Entitled: BL065 - Optometry School - Lab Renovation Rooms 401, 406, 407 (IU20241256)

Owner: Trustees of Indiana University Bloomington, IN 47408

Project Address: Indiana University Bloomington Campus

Prepared By:



Chris W. Lake, AIA

Indiana Registration No. AR10400187

Addendum Dated: 13 May 2025

Project Number: 24-065

CHANGES TO THE PROJECT MANUAL

- 1. DIVISION 23 HEATING, VENTILATING, AND AIR-CONDITIONING (HVAC)
 - a. Section 230952 "HVAC INSTRUMENTATION AND CONTROLS"
 - (1) DELETE Section 230592 in its entirety and replace with the attached Section 230592.

CHANGES TO THE DRAWINGS

- 1. DRAWING SHEETS: ADDITIONS, DELETIONS AND REPLACEMENTS
 - a. Changes as indicated in chart below:

Drawing No.	INDICATE ACTION: REPLACE (r), add (a), delete (d)
M-SERIES DRAWINGS	5
MD101	DELETE AND REPLACE
MH101	DELETE AND REPLACE
MP101	DELETE AND REPLACE
M-601	DELETE AND REPLACE
M-701	DELETE AND REPLACE
M-702	DELETE AND REPLACE

GENERAL CLARIFICATIONS/QUESTIONS

1. What is the size of the freight elevator for stocking?

ANSWER: There is only one passenger elevator so no freight elevator, but see attached PDF showing its cab dimensions.

2. What is the deck height for the fourth floor?

ANSWER: 12'-6" (see attached PDF)

3. What is the allowable deflection for the metal stud framing

ANSWER: L/240

4. What is the seismic category?

ANSWER: B

5. What are the cleaning expectations for the hallway?

ANSWER: Daily mopping is required to keep dust from becoming an issue (tracking throughout the floor and impacting researchers). Mopping around equipment in the hallway will be required.

6. What will be the best approach for loud tasks, i.e. core drilling? Other disruptions?

ANSWER: These types of loud tasks should be prioritized to occur outside of the building's hours of operation (8:00-5:00, Monday thru Friday). The building opens at 6:00 am. 3-day notice is required for power outages and typically these should be prioritized as early as possible to avoid impact to building occupants.

7. Will the communications be "Rough-in" only with UITS providing/installing the communications cabling?

ANSWER: Provide rough-ins only for communications cabling as detailed in the documents. All communications cabling and terminations will be provided by UITS.

8. Can you elaborate on the drying racks requirements and on the adjustable height tables?

ANSWER: These should all be provided by the contractor, the tables are as described on the equipment sheet and are to be in the lab casework scope. The drying racks are also by the lab casework company, there is peg-style drying rack mounted to the side of the existing cabinet and a much smaller wall mounted dish drying rack that can be purchased through Amazon, see image of item name below. The size needed is single tier, wall mount.

Wall Mount Dish Drying Rack, Hanging Dish Racks for Kitchen Dish Drainer with Drain Tray Bowls Plates Coffee Cups Wine Glasses Utensil Holder Small Compact Black Visit the junyuan Store

9. Can the dumpster location be provided?

ANSWER: Image below of desired location from University.

END OF ADDENDUM NUMBER ONE

Page 3

Attachments:

- Pre-Bid Meeting Minutes + Sign-in Sheet (2025-05-07) 1.
- Building Section (depicting deck heights) 2.
- Elevator shop drawings 3.
- Specification Section 230952 4.
- MD101 5.
- 6. MH101
- 7. MP101
- 8. M-601
- 9. M-701
- 10. M-702



05/07/25

Project: IU 20241256 - BL065 - Optometry School - Lab Renovation Rooms 401, 406, 407

DELV Project No: 24-065

Meeting Minutes

Meeting Minutes – Pre-Bid Meeting (IU 20241256)

Date/Time:05/07/25 @ 3:00 pmLocation:Optometry Building – Fourth Floor Lobby

Project Team Attendees:

Jeff Moulden	IU Capital Projects
Diana Short	DELV Design
Lojine Breakah	DELV Design

Contractors Present:

Sign-in to be distributed with Addendum #1

Meeting Agenda (w/ Summary Comments)

- 1. Introductions
- 2. Design Intent (Led by DELV)
 - a. General Project Description
 - b. Architectural/MEP Overview
- 3. Schedule
 - a. Bids Due 05/22/25 @ 2:00pm
 - b. Questions to be submitted by 2:00pm on Thursday, May 15, 2025.
 - c. Construction Complete 9/1/2025 for Lab 406 and 11/21/2025 for the remainder of the scope.
- 4. Construction (led by IU)
 - a. Use of Site
 - i. Access

^{1.} All contractor personnel must have a Crimson Card.

- 2. IU Indy will provide construction cores where needed
- 3. Parking with tags in marked lots.
- 4. Loading and unloading is where?
- 5. Staging will need to be within the space.
- 6. Dumpster location?
- 7. Cleaning and noise requirements
- 8. Bi-Weekly meetings during construction
- 9. E-Builder will be used for most CA processes.
 - a. Submittals will be via email with the final approved copy uploaded to E-Builder.
- Addendums will be issued as needed. Addendum #1, to include Pre-bid Meeting Minutes, will be issued on 05/13/24.
- 6. Q/A-




IU PROJECT NO. IU 20241256-blo65 DELV PROJECT NO. 24-065

07 MAY 2025


IUB Optometry School - Lab Renovation Rooms 401, 406, 407 PRE-CONSTRUCTION MEETING SIGN-IN SHEET


Name + Company	Email	Phone
Diana Short – DELV	diana@DELVdesign.com	(317) 296-7400
Lojine Breakah	Lojine@DELVdesign.com	
Chris Kelley Electric Plus	ckelley Delatriplus an	877-325-3048
The Hownsons	IU OPF	812-355-6489
LANNY Lee	LARRY & LOSE, CONST	c-cal com 317-66-75 Notiver 317-908-7892
Rud Sills	15:115@weddlebros.com	812-320-7283
Mallory Halcomb	MhalcombaHarrell-Fish	
Andy Hays	ahays@sparton.mechanice	.net (812)327-3598
JEFF MOULDER?	JMOULDER W. EN	312-320-0021
	2	





	h.
5 × 3% × 3% 2 CONT. % × % LUG AARHAR 3/4 & RODI AR BOLTS 24	
12'-0" Mioi	
U Losveiz U B-7 E-N V.	
378×11 PECELUES & FLACED 1910 FANT	KO OF BOLTS ANGH
too po to	
BLECK	
	CENT. 3 8 - 11
NOTE: SET EDGE 5	
TIN CAULKING UHEREVER AREA ABOUE IS USED AS A BETURN PLENUM	
UNINYL CHALK BEARDE	
RM 155 DETAIL SHE BA	Court 19/8 x 11 / 2100
1/21.0. PIPE	
	¥
SECTION LOOKING EAST BETWEEN Cor's, 16 417	
SCALE 1/4' + 1'-O"	







1AT	ERIALS AND FII	WEIGHT: 1911 LBS
A	DOORS	42" X 84" DOUBLE SPD SSL LH, 1 1/4" DOOR CORE CLAD
		4 SATIN STAINLESS STEEL [16GA] (2 GIBS PER DOOR PANEL)
В	FRONTS	(1) STATIONARY RETURN; (1) STRIKE
0	I KONI J	AND (1) FULL WIDTH TRANSOM #4 SATIN ST. STEEL [16GA]
		AND (1) TOLL WIDTT TRANSOW #4 SATIN ST. STELL [TOGA]
С	SHELL	GALVANIZED STEEL [14GA]
C	SHELL	GALVANIZED SIELE [14GA]
<u> </u>		
D	WALL PANELS	VERTICAL, REMOVABLE CLASS B,
		3/4" FRPB W/ BALANCE BACKER FACED AND EDGED ON
		VERTICAL SIDES W/ 5WL RIGIDIZED STAINLESS STEEL[16 GA]
F	REVEALS/BAS	BETWEEN & BELOW PANELS #4 SATIN ST. STEEL [20GA]
G	UPPER CEILING	G W/ HINGED EMERGENCY EXIT, PAINTED STEEL [12GA]
Н	LOWER CEILIN	G W/ LIFTOUT EXIT, 3/4" F.R.P.B.
		MULTIPLE SECTIONS FACED W/ #4 SATIN ST. STL. [20GA]
		L
J	LIGHTING	(6) UNIT MAN-D-TEC WARM WHITE
-		3000K DOWNLIGHTS W/ BLACK TRIM & DIMMER
К	HANDRAILS/B	UMPERRAILS TWO ROWS @ REAR AND SIDE
ĸ	TIANDRAIL3/D	WALLS 3/8" X 2" STAINLESS STEEL BAR WITH STRAIGHT ENDS
		WALLS 5/6 X 2 STAINLESS STELE BAR WITT STRAIGHT LINDS
K2		
κz	RAIL BRACKET	
		WITH 2" X 2" REINFORCEMENT PLATES
L	SILL	5 1/2" X 67" ALUMINUM
М	FAN	MAN-D-TEC STD. TWO SPEED FAN WITH BAFFLE
Ν	PAD HANGER	S ST. STL. STUD TYPE @ WALLS & RETURN
-	HEADER ANG	LE/ OPERATOR SUPPORT BY G&R
-	EMERGENCY LIC	GHTING MAN-D-TEC ELS-SB INTEGRAL WITH DOWNLIGHTS
		PRINT RECORD
	7/04/10	

	PRINT RECO	RD	
7/24/19	(1) APPROVAL		
8/13/19	(1) REV. APPROVAL		
B NAME	E: IU SCHOOL OF OPTOME	TRY	
R(S) #	1 C	APACITY:	2500#
ATION	BLOOMINGTON, IN		
TOMER	: AMERICAN ELEVATOR, II	NC.	
	8/13/19 B NAMI R(S) # CATION	7/24/19 (1) APPROVAL 8/13/19 (1) REV. APPROVAL 8 NAME: IU SCHOOL OF OPTOME R(S) # 1 C. CATION: BLOOMINGTON, IN	8/13/19 (1) REV. APPROVAL 8 1 8 NAME: IU SCHOOL OF OPTOMETRY 8 1 CAPACITY:


	CUSTOMER#: IU OPTOMETRY
IS&R	DRAWN BY: KPE 7/23/2019
Custom Elevator Cabs	Sheet 1 of 5
2352 STATION PARKWAY NW	JOB NO.:
ANDOVER, MN 55304	JOB NO
PHONE: 763-757-6177	21382
FAX: 763-757-6420	21002



PAD HANGER LOCATIONS



ELEVATION A




ELEVATION B & D




PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF G &R CUSTOM ELEVATOR CABS. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITEIN PERMISSION OF G &R CUSTOM ELEVATOR CABS IS PROHIBITED.



PAD HANGER LOCATIONS

CAR(S) # 1 CAPACITY: 2500# LOCATION: BLOOMINGTON, IN CUSTOMER: AMERICAN ELEVATOR, INC.
CUSTOMER: AMERICAN ELEVATOR, INC.
CUSTOMER#: IU OPTOMETRY
DRAWN BY: KPE 7/23/2019
Custom Elevator Cabs SHEET 3 OF 5
2352 STATION PARKWAY NW ANDOVER, MN 55304 JOB NO.:
PHONE: 763-757-6177 21382
FAX: 763-757-6420




SIZE B

PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF G &R CUSTOM ELEVATOR CABS. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF G &R CUSTOM ELEVATOR CABS IS PROHIBITED.

CAR(S) # 1 CAPACITY: 2500# LOCATION: BLOOMINGTON, IN CUSTOMER: AMERICAN ELEVATOR, INC.
CUSTOMER: AMERICAN ELEVATOR, INC.
CUSTOMER#: IU OPTOMETRY
DRAWN BY: KPE 7/23/2019
2352 STATION PARKWAY NW JOB NO.:
ANDOVER, MN 55304
PHONE: 763-757-6177 21382 FAX: 763-757-6420



REFLECTED UPPER CEILING PLAN



PROPRIETARY AND CONFIDENTIAL

THE INFORMATION CONTAINED IN THIS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. Section 23 01 00 "Basic Mechanical Requirements," and Section 23 05 00 "Basic Mechanical Materials and Methods" all apply to the work of this Section as if fully repeated herein.

1.2 SUMMARY

- A. This Section includes control equipment for HVAC systems and components, including control components for terminal heating and cooling units not supplied with factory-wired. controls.
- B. Controls Installation Contractor (CIC) is to receive, install, connect and test devices that are purchased directly from Siemens by the University.
- C. Mechanical contractor to install control valves.
- D. Mechanical contractor to provide necessary sensor wells and gauge taps.
- E. Electrical contractor is to provide 120/60 VAC power to DDC panels. CIC is to install power from available 120V circuits at panels boards to controllers and actuators (provide transformers as necessary).
- F. Electrical contractor is to provide and install variable frequency drives and associated connections for power (to VFD and from VFD to motor) except when drives are factory-mounted and factory-wired. CIC to install low-voltage control signal cabling to VFDs.
- G. Sheet metal contractor is to install automatic dampers.

1.3 SEQUENCE OF OPERATION

A. A DDC Points List and a written Sequence of Operation for each system appears on the Construction Documents.

1.4 SUBMITTALS

- A. Product Data: Include manufacturer's technical literature for each control device. Indicate dimensions, capacities, performance characteristics, electrical characteristics, finishes for materials, and installation and startup instructions for each type of product indicated.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 1. Bill of materials of equipment indicating quantity, manufacturer, and model number.
 - 2. Schematic flow diagrams coils, dampers, valves, and control devices.
 - 3. Wiring Diagrams: Power, signal, and control wiring.
 - 4. Details of control panel faces, including controls, instruments, and labeling.

	•		•		
IU Project #: 20241256		230952		HVAC Instrumentation and	
BL065 Optometry School				Controls	
Lab Renovation Rooms 401, 406, 407					

- 5. Written description of sequence of operation.
- 6. Schedule of dampers including size, leakage, and flow characteristics.
- 7. Schedule of valves including flow characteristics.
- 8. DDC System Hardware:
 - a. Wiring diagrams for control units with termination numbers.
 - b. Schematic diagrams and floor plans for field sensors and control hardware.
 - c. Schematic diagrams for control, communication, and power wiring, showing trunk data conductors and wiring between operator workstation and control unit locations.
- 9. Controlled Systems:
 - a. Schematic diagrams of each controlled system with control points labeled and control elements graphically shown, with wiring.
 - b. Written description of sequence of operation including schematic diagram.
 - c. Points list.

1.5 QUALITY ASSURANCE

- 2
- A. Installer Qualifications: Automatic control system manufacturer's authorized representative who is trained and approved for installation of system components required for this Project.

PART 2 - PRODUCTS

2.1 CONTROL SYSTEM

- A. Indiana University, the Owner, will pre-purchase directly from Siemens Building Technologies the following equipment for the building automation system:
 - 1. Direct Digital Control panels.
 - 2. Auxiliary panels with internal components pre-wired.
 - 3. All required sensing devices (i.e.: temperature, C02 sensors).
 - 4. Safety devices: low temperature detectors.
 - 5. Valves, valve actuators.
 - 6. Dampers, damper actuators.
 - 7. Relays.
 - 8. Transformers.
 - 9. Thermostats.
 - 10. Variable Frequency Drives.
 - 11. All necessary design engineering labor.
 - 12. All necessary technician labor to verify point wiring, program and start up all DDC panels, perform acceptance testing.
 - 13. Project management labor required to direct the CIC and attend job meetings.
 - B. During the bidding process, the Control Installation Contractor (CIC) shall address all questions relative to the Siemens drawings to Siemens Building Technologies Inc. directly in writing. Siemens shall respond in writing with a copy to the consulting engineer and to Indiana University Architects Office, attention Mr. P.K. Patel.
 - C. All products pre-purchased by the Owner, as listed above, will be shipped to the (CIC) Control Installation Contractor for installation and wiring. The CIC shall receive, handle and store all material to be installed under this contract. The CIC shall be responsible for verification of quantity received. Any discrepancies shall be reported in writing to Siemens Building Technologies, Inc. within 48 hours of delivery.

- D. CIC shall install all control equipment provided by the Owner. The CIC shall furnish, install, and terminate all necessary wiring, conduit, hangers, etc. to provide a complete control system installation. All controls to be installed and adjusted by trained mechanics in the full time employ of the CIC.
- E. Upon completion of all installation and wiring by the CIC the Owners agent (Siemens Building Technologies) will conduct verification of point-to-point wiring and pneumatic tubing. The CIC will be responsible to make any necessary corrections. At the completion of the point-to-point verification, approval shall be made by the Owner's Construction Inspection Department and Siemens Building Technologies, Inc.
- F. Upon approval by the Owners Construction Inspection Department, the Owner's agent shall program all DDC panels, create necessary graphics and provide any interface between the building automation system and the campus environmental control system.
- G. Upon completion of the aforementioned, a performance test shall be conducted as specified in Section 5.0 On-site Testing.
- H. Upon a successful conclusion of the final checkout, performance test and the Owner's acceptance, the CIC's responsibility reverts to a standard 24-month warranty for labor and material installed by the CIC and labor only for equipment supplied by others.
- I. The Owner's agent (Siemens Building Technologies, Inc.) assumes the manufacturer's warranty for all equipment supplied to the CIC on this project.
- J. Siemens shall supply the following directly to Indiana University:
 - 1. Design Engineering labor required to interface with IC and the consulting engineer to design the temperature control system.
 - 2. Supervision of the CIC installation and final checkout and approval.
 - 3. Project management labor to attend job meetings and ensure construction time compliance and settlement of any conflicts.
 - 4. Technician labor required for point to point check out, software programming, graphics creation and Owner training.
 - 5. All material listed in 2.1, A.
 - 6. During the warranty period, Siemens will respond to all requests rendered by the Owner for satisfactory operation of the system.
- K. Control system shall consist of sensors, indicators, actuators, final control elements, interface equipment, other apparatus, and accessories to control mechanical systems.
- L. Control system shall consist of sensors, indicators, actuators, final control elements, interface equipment, other apparatus, accessories, and software connected to distributed controllers operating in multiuser, multitasking environment on token-passing network and programmed to control mechanical systems. A local or remote operator workstation permits interface with the network via dynamic color graphics with each mechanical system, building floor plan, and control device depicted by point-and-click graphics.

2.2 DDC EQUIPMENT

- A. Application Software: Provide all required updates to application software for existing campus operator workstations to ensure complete interoperability with existing Siemens systems, as applicable.
- B. Central (Master) Control Units: Modular, comprising processor board with programmable, nonvolatile, random-access memory.
 - 1. Units monitor or control each input/output point; process information; execute commands from other control units, devices, and operator stations; and download from or upload to operator station.
 - 2. Stand-alone mode control functions operate regardless of network status. Functions include the following:
 - a. Global communications.
 - b. Discrete/digital, analog, and pulse input/output.
 - c. Monitoring, controlling, or addressing data points.
 - d. Testing and developing control algorithms without disrupting field hardware and controlled environment.
- C. Local Control Units: Modular, comprising processor board with electronically programmable, non-volatile, read-only memory; and backup power source.
 - 1. Units monitor or control each input/output point; process information; and download from or upload to operator station.
 - 2. Stand-alone mode control functions operate regardless of network status. Functions include the following:
 - a. Global communications.
 - b. Discrete/digital, analog, and pulse input/output.
 - c. Monitoring, controlling, or addressing data points.
- D. Software: Update to latest version of software at Project completion. Include and implement the following capabilities from the control units:
 - 1. Units of Measure: Inch-pound and SI (metric).
 - 2. Load Control Programs: DDC with fine tuning, and trend logging.
 - 3. Programming Application Features: Include trend point, alarm messages, weekly scheduling, and interlocking.

2.3 CONTROL PANELS

- A. Control Panels: Fully enclosed standard metal or plastic cabinet with locking doors or locking removable backs. Match finish of panels.
- B. Local Control Panels: Unitized cabinet with suitable brackets for wall or floor mounting, located adjacent to each system under automatic control. Provide common keying for all panels.
 - 1. Fabricate panels of 0.06-inch-thick, furniture-quality steel, or extruded-aluminum alloy, totally enclosed, with hinged doors and keyed lock and with manufacturer's standard shoppainted finish.
 - 2. Panel-Mounted Equipment: Temperature and humidity controllers, relays, and automatic switches; except safety devices. Mount devices with adjustments accessible through front of panel.
 - 3. Door-Mounted Equipment: Flush-mount (on hinged door) manual switches, including damper-positioning switches, changeover switches, thermometers, and gages.

2.4 DDC CONTROLLERS

A. Each stand-alone DDC Controller shall be able to extend its performance and capacity through the use of remote Application Specific Controllers (ASCs).

- B. Each ASC shall operate as a stand-alone controller capable of performing its specified control responsibilities independently of other controllers in the network. Each ASC shall be a microprocessor-based, multi-tasking, real-time digital control processor.
- C. Each ASC shall have sufficient memory to support its own operating system and data bases including:
 - 1. Control Processes.
 - 2. Energy Management Applications,
 - 3. Operator I/O.
- D. The operator interface to any ASC point data or programs shall be through any networkresident PC workstation, or any PC or portable operator's terminal connected to any DDC panel in the network.
- E. Application Specific Controllers shall directly support the use of a portable terminal. The capabilities of the portable terminal shall include but not be limited to the following:
 - 1. Display temperatures.
 - 2. Display status.
 - 3. Display set-points.
 - 4. Display control parameters.
 - 5. Override binary output control.
 - 6. Override analog set-points.
 - 7. Modification of gain and offset constants.
- F. Power fail Protection: All system set-points, proportional bands, control algorithms, and any other programmable parameters shall be stored such that a power failure of any duration does not necessitate reprogramming the controller.
- G. Configuration and Download: The ASCs shall have the capability of receiving configuration and program loading by both of the following: 1) locally, via a direct connect portable laptop service tool, 2) over the network, from the portable laptop service tool, and; 3) from the Operation Workstation, via the communication networks.
- H. Continuous Zone Temperature Histories: Application Specific Controllers shall have the capability to automatically and continuously maintain a history of the associated zone temperature to allow users to quickly analyze space comfort and equipment performance for the past 24 hours. A minimum of two samples per hour shall be stored.
- I. Extended Digital Controllers: Extended Digital Controllers shall provide all of the capabilities defined above for the ASCs. In addition, they shall include the following features:
 - 1. Extendable input and output points.
 - 2. Customizable graphic software programming of control sequences.

2.5 SENSORS

- A. Electronic Sensors: Vibration and corrosion resistant for wall, immersion, or duct mounting as required.
 - 1. Resistance Temperature Sensors and Transmitters: Platinum or nickel.
 - a. Accuracy: Plus or minus 0.2 percent at calibration point.
 - b. Wire: Twisted, shielded-pair cable.

- c. Insertion Elements in Ducts: Use where not affected by temperature stratification or where ducts are smaller than 9 sq. ft.
- d. Averaging Elements in Ducts: Use where prone to temperature stratification or where ducts are larger than 9 sq. ft., length as required.
- e. Insertion Elements for Liquids: Brass socket with minimum insertion length of 2-1/2 inches.
- f. Space Temperature Sensors: Mount beneath a thermostat cover with local set-point adjustment.
- Carbon Dioxide Sensor and Transmitter: Single detectors, using solid state infrared sensors, suitable over a temperature range of 23 to 130 degrees F (minus 5 to plus 55 C), calibrated for 9 to 2 percent, with continuous or averaged reading, 4 to 20 mA output, and suitable for wall-mounting, as indicated.

2.6 ACTUATORS

- A. Electric Motors: Size to operate with sufficient reserve power to provide smooth modulating action or two-position action. Actuators shall be manufactured by Siemens.
- B. Permanent Split-Capacitor or Shaded-Pole Type: Gear trains completely oil immersed and sealed. Equip spring-return motors with integral spiral-spring mechanism in housings designed for easy removal for service or adjustment of limit switches, auxiliary switches, or feedback potentiometer.
- C. Electronic Damper and Large-Valve Actuators: Direct-coupled type designed for minimum 60,000 fully-stroke cycles at rated torque.
 - 1. Valves: Size for torque required for valve close-off at maximum pump differential pressure.
 - 2. Dampers: Size for running torque calculated as follows:
 - a. Dampers with 2 to 3 Inches wg of Pressure Drop or Face Velocities of 1000 to 2500 FPM: Multiply the minimum full-stroke cycles above by 1.5.
 - Dampers with 3 to 4 Inches wg of Pressure Drop or Face Velocities of 2500 to 3000 FPM: Multiply the minimum full-stroke cycles above by 2.0.
 - 3. Coupling: V-bolt and V-shaped, toothed cradle.
 - 4. Overload Protection: Electronic overload or digital rotation-sensing circuitry.
 - 5. Fail-Safe Operation: Mechanical, spring-return mechanism. Provide external, manual gear release on non-spring-return actuators.
 - 6. Power Requirements (Modulating): Maximum 10 VA at 24-V ac or 8 W at 24-V dc.
 - 7. Proportional Signal: 2- to 10-V dc or 4 to 20 mA, and 2- to 10-V dc position feedback signal.

2.7 CONTROL VALVES

- A. Control Valves: Factory fabricated, of type, body material, and pressure class based on maximum pressure and temperature rating of piping system, unless otherwise indicated.
- B. Globe or Ball Valves NPS 2 and Smaller: Bronze body, bronze trim, and screwed ends.

PART 3 – EXECUTION

3

3.1 EXAMINATION

IU Project #: 20241256 BL065 Optometry School Lab Renovation Rooms 401, 406, 407

- A. Verify that conditioned power supply is available to control units.
- B. Verify that duct, pipe, and equipment-mounted devices and wiring are installed before proceeding with installation.

3.2 DDC CONTROL SYSTEM INSTALLATION

- A. Install equipment level and plumb.
- B. Install software in control units. Implement all features of programs to specified requirements and as appropriate to sequence of operations indicated on the Drawings.
- C. Connect and configure equipment and software to achieve sequence of operations specified on the Drawings.
- D. Verify location of space temperature sensors, and other exposed control sensors with plans and room details before installation. Locate all 48 inches above the floor (align horizontally with light switches), unless indicated otherwise on the Drawings.
 - a. Install averaging elements in ducts and plenums in crossing or zigzag pattern.
- E. Install labels and nameplates to identify control components according to Division 23 Section "Identification for HVAC Piping and Equipment."
- F. Install hydronic instrument wells, valves, and other accessories according to Division 23 Section "Hydronic Piping."

3.3 ELECTRICAL WIRING AND CONNECTION INSTALLATION

- A. Install raceways, boxes, and cabinets according to Division 26 Section "Raceways, Boxes, and Cabinets."
- B. Install building wire and cable according to Division 26 Section "Conductors and Cables."
 - 1. All control cable wiring shall be installed in the raceway. See Div. 026 for raceway specifications.
 - 2. Conceal cable, except in mechanical rooms and areas where other conduit and piping are exposed.
 - 3. Concealed and accessible cable shall be jacketed plenum rated cable.
 - 4. Bundle and harness multiconductor instrument cable in place of single cables where several cables follow a common path.
 - 5. Fasten flexible conductors, bridging cabinets and doors, along hinge side; protect against abrasion. Tie and support conductors.
 - 6. Number-code or color-code conductors for future identification and service of control system, except local individual room control cables.
 - 7. Connect manual-reset limit controls independent of manual-control switch positions.
 - 8. Connect hand-off-auto selector switches to override automatic interlock controls when switch is in hand position.

3.4 CONNECTIONS

- A. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
 - 1. Install piping adjacent to machine to allow service and maintenance.
- B. Ground Equipment
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturers torque values are not indicated, use those specified in UL 486A and UL 486B.

3.5 FIELD QUALITY CONTROL

- A. Manufacturers Field Service: Engage a factory-authorized service representative to inspect field-assembled components and equipment installation, Report results in writing.
 - 1. Test and adjust controls and safety. Replace damaged and malfunctioning controls and equipment, and retest.
- B. Engage a factory-authorized service representative to perform startup service.
- C. Replace damaged or malfunctioning controls and equipment.
 - 1. Start, test, and adjust control systems.
 - 2. Demonstrate compliance with requirements. including calibration and testing, and control sequences.
 - 3. Adjust, calibrate, and fine tune circuits and equipment to achieve sequence of operation specified on the Drawings.
- D. Verify DDC as follows:
 - 1. Verify software including automatic restart, control sequences, scheduling, reset controls, and occupied/unoccupied cycles.
 - 2. Verify local control units including self-diagnostics.

3.6 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain control systems and components.
 - 1. Train Owner's maintenance personnel on procedures and schedules for starting and stopping, troubleshooting, servicing, and maintaining equipment and schedules.

END OF SECTION 230952

SIEMENS

SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION

3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268 UNITED STATES

PHONE: 317-293-8880 FAX: 317-293-0374

05/09/25

FOR INFORMATION CONTACT ERIC HUGHES

ENGINEERING DATA FOR BL065 OPTOMETRY SCH-LAB RENO

INDIANA UNIVERSITY BLOOMINGTON IU PROJECT #20241256, IN 47405 USA

440P-398851

DELV DESIGN ARCHITECT

CREATIVE ENGINEERING SOLUTION ENGINEER

INDIANA UNIVERSITY CONTRACTOR

DWG DESCRIPTION

GENERAL

CVRST	COVER SHEET
CIC	C.I.C CONTRACTOR NOTES
LEG	Legend & Abbreviations
ABAC	Anixter Building Auto. Cables
FLCT	FLNC Termination Specification
FTRM	FLN Termination Specification
TTRM1	TX-I/O Termination Spec.
TTRM2	TX-I/O Termination Spec. 2
TTRM3	TX-I/O Termination Spec. 3
	SCHEDULE
VLV	CONTROL VALVE SCHEDULE

VLV	CONTROL VALVE SCHEDULI
	LGE SCHEDULE
LAB	LB ROOM SCHEDULE

CONTROL DRAWINGS

R01	SYSTEM RISER
R02	POWER TRUNK
R02A	POWER TRUNK BOM
100	LEF-3 CONTROL
100A	LEF-3 ELEC. WIRING
100B	EXISTING RTU-3 AUX PANEL
100C	LEF-3 CONTROL BOM & SOO
400	1SAV-1EAV-SLOW-LCM

DWG DESCRIPTION

CONTROL DRAWINGS

400A	1SAV-1EAV-SLOW-LCM ELEC. WIRING
400B	1SAV-1EAV-SLOW-LCM BOM & SOO
401	LAB ROOM 406 CONTROL
401A	LAB RM 406 ELEC. WIRING
401B	LAB RM 406 CTRL BOM & SOO
410	1SAV-1EAV-FAST-LCM
410A	1SAV-1EAV-FAST-LCM ELEC. WIRING
410B	1SAV-1EAV-FAST-LCM BOM & SOO
420	FUME HOOD CONTROL
420A	FH CONTROL ELEC. WIRING
420B	FH CONTROL BOM & SOO
430	VAV w/HW REHEAT
430A	VAV w/HW REHEAT BOM & SOO

DDC PANEL LAYOUTS

	W. 4th Fl. Labs
	Optometry RTU-3 Node 3p002
900B	Optometry RTU-3 Node 3p003

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880	BL065 OPTOMETRY SCH-LAB RENO	
00 5/9/2025 HB SUBMITTAL SET	SIEMENS INDUSTRY INC.		IU PROJECT #20241256, IN ENGINEER DRAFTER CHECKED BY INITIAL RELEASE LAST EDIT DATE HB HB 05/09/25 05/09/25 05/09/25	
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	Table of Contents	

44OP398851 0

© COPYRIGHT 1994-2025 SIEME	ENS INDUSTRY INC. ALL RIGHTS RESERVED		ASTRUCTURE DIVISION	FAX: 317-293-0374	Legend & Abbre	eviations
00 5/9/2025	HB SUBMITTAL SET	 Siemens ind	oustry inc.	INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880		ED BY INITIAL REL 05/09/
REVISION		SIEME	NS	3502 WOODVIEW TRACE SUITE 240	BL065 OPTOMETRY	
	PUINT NUMBER		NOTE OR REVISION	REFERENCE NU NODE NUMBE FLN TRUNK DROP NUMBE POINT NUMBE	JMBER	■ DIGITAL
CABINET NUME LAN TRUNK DROP NUMBER POINT NUMBER	LAN TRUNK DROP NUMBER	DETAIL	PNEUMATIC TERMIN	ATION	T NAME - AHILID [0001: 3.10.27] DETAIL 5A : DETAIL MC .	READ A
	R [0]00100000 [0]00100 [0]001000 [0]001000 [0]001000 [0]001000 [0]001000 [0]001000 [0]001000 [0]0010000 [0]001000 [0]0010000 [0]001000 [0]00000 [0]0000 [0]0000 [0]00000 [0]00000 [0]000000 [0]0000000 [0]0000000 [0]00000000		ELECTRICAL TERMIN	AF UGLL.	ETHERNET – EXAMPLE T NAME – AH1LTD	
HE	HUMIDIFIER ELECTRIC ELECTRICAL POINT DDC PNEUMATIC POINT	\$	DETAILS	CABINET N FLN TRUNK DROP NUM POINT NUM	BER	
FS FTP G GD H	FLOW SWITCH FLOW TRANSMITTER PNEU. GAUGE GAS DETECTOR HYGROSTATS	PXG3 RBC RC	BACNET ROUTER ETHERN REMOTE BUILDING CONTR RECEIVER CONTROLLER	ROLLER BLN NUMB	0.10.3.10.27 DETAIL 5A DETAIL MC ER	READ
FAN FHC FM FMS	FAN FUME HOOD CONTROLLER FLOW MTR. (FLOW METER STATION) FIRE MGMT. SYSTEM	PTR PV PXCC PXCCM	PRINTER PILOT VALVE PX COMPACT CONTROLLE PXC-MODULAR CONTROL	LER LOCICAL R	DGEE: PII — EXAMPLE DINT NAME — AH1LTD	
EP ES ET EXP	ELECTRO-PNEUMATIC VALVE END SWITCH ENTHALPY TRANSMITTER EXPANSION PANEL	PST PT PTE PTP	PULL STATION PITOT TUBE PRESSURE TRANSMITTER PRESSURE TRANSMITTER		W WS XDf XFN	r tran
DPTP DPU DXR EC	DIFFERENTIAL PRESSURE PNEUMATIC DIGITAL POINT UNIT TERMINAL EQUIPMENT CONTROLLER ENTHALPY COMPARITOR	PRC PRV PS PSE	PRESSURE REG. CONTRO PRESSURE REDUCING VA POSITIONING SWITCH POSITION SENSOR ELECT	LVE	VA VA VB VTE	C VARI. VIBR. E VELO
DP DPR DPS DPTE	DEW POINT TRANSMITTER DIFFERENTIAL PRESS. REGULATOR DIFFERENTIAL PRESSURE SWITCH DIFF. PRESS. TRANSMITTER ELEC.	PL PM PNL PPM	PILOT LIGHT POWER MONITOR PANEL POINT PICKUP MODULE		UC UV V V*	C UNIT
D D DDC DEM	CONSTANT VOLUME CONTROLLER DAMPER DUAL DUCT CONTROLLER DEMAND ENERGY MONITOR	P PA PCT PE	PUMP PULSE ACCUMULATOR PROGRAMMABLE CLOCK PRESSURE ELECTRIC SWI		TTE TTF TXI UC	TEMP TEMP TEMP TX-1
CRT CS CT CTE	CATHODE RAY TUBE CURRENT SWITCH CURRENT TRANSDUCER CO2 TEMP TRANSMITTER ELEC	OCC OCCB OBS ODP	OCCUPANCY OCCUPANCY AND BRIGH OBSOLETE OPERATOR DATA PANEL	TNESS	TI TIE TIU TMI	TRUN TRUN TELC
CKV CM CP CPU	CHECK VALVE CONSTRUCTION MATERIALS COMPONENT PANEL CENTRAL PROCESSING UNIT	MEC MG MPU MS	MODULAR EQUIPMENT CO MAGNEHELIC GAUGE MULTI-POINT UNIT MOTOR STARTER	DNTROLLER	TDF TE TE TE TH	R TIME THER C TERN
BRT BRTT BTN CBL	BRIGHTNESS BRIGHTNESS AND TEMPERATURE BUTTON CABLES	LUI MBC MDM ME	LOCAL USER INTERFACE MODULAR BUILDING CON MODEM ELECTRONIC ACTUATOR		T T TBC TC TC	ROOM C TERM TEMF
BCU BELL BIM BOIL	BUS COUPLING UNIT BELL BUS INTERFACE MODULE BOILER	LLT LPR LTDE LTDP	LIQUID LEVEL TRANS. POWER SUPPLY 24VAC/ LOW TEMP. DETECTOR EL LOW TEMP. DETECTOR PI	LECTRIC	SPI SPI SV SV	P STAT R STAT SOLE
AT ATD ATC ATEC AZM	AUTOMATIC TRAP AUTO TANK DRAIN ACTUATOR TEC AUTOZERO MODULE	KWM LA LC LLS	ELECTRIC KILOWATT METH LIGHT ACTUATOR LIMIT CONTROLLER (LIMIT LIQUID LEVEL SWITCH		SE SIC SL) SPI	SWIT SLX (APO(
AFS AOP AP APS	AIR FLOW STATION ANALOG OUTPUT, PNEUMATIC ACTUATOR PNEUMATIC AUX. POWER SUPPLY	HTD HTE HTP INT	HIGH TEMPERATURE DETI HUMIDITY TRANSMITTER I HUMIDITY TRANSMITTER I INTERCOM	ECTOR ELECTRIC	SA SC SC SD	SHAI STEF J STAN
ADXR AE AEM AF	ACTUATOR DXR ACTUATOR ELECTRIC APOGEE ETHERNET MICROSERVER AIR FILTER	HMI HOA HORN HPC	GAMMA TOUCH PANEL HAND-OFF-AUTO SWITCH HORN HEAT PUMP CONTROLLEF		RP RS RV S/	RELA REST RELIE
SYMBOL AC AD	DESCRIPTION AIR COMPRESSOR AIR DRYER	SYMBOL HHC HL	DESCRIPTION HAND-HELD OPERATOR'S HIGH LIMIT	s terminal	SYI RCI RE	
CONTROL	CONTROL SYMBOL	CONTROL	CONTROL SYMBOL			NTROL CON

CONTROL SYMBOL DESCRIPTION REMOTE CONTROL UNIT RELAY ELECTRIC RELAY PNEUMATIC RESTRICTOR RELIEF VALVE SOFTWARE SHADE ACTUATOR STEP CONTROLLER STAND ALONE CONTROL UNIT SMOKE DETECTOR SWITCH ELECTRIC SLX IO MODULES APOGEE SLX CONTROLLER SPEAKER STATIC PRESSURE PROBE STATIC PRESSURE REGULATOR SOLENOID VALVE SWITCH PNEUMATIC ROOM THERMOSTAT, PNEUMATIC TERMINAL BOX CONTROLLER TEMPERATURE CONTROLLER(S200) TERMINAL CONTROL UNIT TIME DELAY RELAY THERMOSTAT, ELECTRIC TERMINAL EQUIPMENT CONTROLLER THERMOMETER TRUNK INTERFACE TRUNK ISOLATOR EXTENDER TELCOM INTERFACE UNIT TIMER, TIME CLOCK TEMPÉRATURE TRANSMITTER ELECTRIC TEMPERATURE TRANSMITTER PNEUMATIC TX-I/O FAMILY CONTROLLER MODULES UNITARY CONTROLLER UNIT CONDITIONER CONTROLLER UNIT VENT CONTROLLER VALVE VALVE SERVICE PARTS TEC VALVE ACTUATOR VARIABLE AIR VOLUME CONTROLLER VIBRATION ISOLATOR VELOCITY TRANSMITTER ELECTRICAL WELL WEATHER STATION TRANSDUCER TRANSFORMER ---- DIGITAL INPUT READ AS " SEE PAGE 5A FOR MORE DETAIL " DIGITAL INPUT I-LAB RENO 440P398851 0 INITIAL RELEASE LAST EDIT DATE 05/09/25 05/09/25 LEG

FLNC WIRING TYPE AND GAUGE REQUIREMENTS TABLE 1

TABLE 1					
CIRCUIT TYPE	CLASS	WIRE TYPE	MAX. DISTANCE	CONDUIT SHARING	
AC LINE POWER (FLNC)	Power	#12–14 THHN	AS REQUIRED	CHECK LOCAL CODES	
DIGITAL OUTPUT	1	CHECK LOCAL CODES	SEE TABLE 4	CHECK LOCAL CODES	
DIGITAL OUTPUT	2	CHECK LOCAL CODES	SEE TABLE 4	CHECK LOCAL CODES	
DIGITAL INPUT	2	#18-22 TP	750ft (230 m)	CLASS 1 & 2 CHECK LOCAL	
ANALOG INPUT THERMISTOR	2	#18-22 TP	100ft (30.5 m)	CODES CLASS 1 & 2 CHECK CODES	
LAN TRUNK ¹	2	#18-22 AWG TSP	4kft (1220 m)	CLASS 2 ONLY	

TABLE 1A NOTES:

1. WHEN A TIE IS USED ON A LAN TRUNK, THE LAN TRUNK CAN BE EXTENDED ANOTHER 4000-5000 FEET (DEPENDING ON WIRE GAUGE). USING THREE TIE'S ON ONE FIELD PANEL COULD ALLOW A MAXIMUM OF 16,000 FEET OF #20 TSP WIRE (THE LOCAL 4000 PLUS 4000 FOR EACH TIE).

DI, AI, AO WIRE SPECIFICATIONS

TABLE 2

SPECIFICATION	WIRE	TYPE
SPECIFICATION	SHIELDED	UNSHIELDED
CAPACITANCE WIRE TO WIRE	NOT SPECIFIED	NOT SPECIFIED
CAPACITANCE BETWEEN ONE CONDUCTOR WITH OTHER CONDUCTOR CONNECTED TO SHIELD	NOT SPECIFIED	N/A
WIRE LAY	2" MAX.	2" MAX.
AWG	18-22	18-22

TABLE 2 & 4 NOTES:

1. OPTIMAL NOISE REDUCTION IS ACHIEVED WITH TIGHTER WIRE LAYS (E.G. 1/2").

LAN	TRUNK	WIRE
	TABLE 3	

THELE S					
	LENGTH OF TRUNK SECTION				
SPECIFICATION	4000 FT	10,000 FT			
CAPACITANCE WIRE TO WIRE	60pF MAX.	24pF MAX.			
CAPACITANCE BETWEEN ONE CONDUCTOR WITH OTHER CONDUCTOR CONNECTED TO SHIELD	100pF MAX.	44pF MAX			
WIRE LAY	2" MAX.	2" MAX.			
AWG	18-22	18 MIN.			

TABLE 3 NOTES:

1. DISTANCES SHOWN ASSURE LESS THAN 10% VOLTAGE DROP ACROSS THE WIRE FOR A TYPICAL STARTER.

MAXIMUM DO WIRE RUN LENGHTS table 4					
NOMINAL	STARTER		WIRE SIZE		
INRUSH	SIZE	<i>#</i> 18	# 16	#14	
200 VA	0 1	500ft (152m)	900ft (274m)	1400ft (427m)	
550 VA	2	200ft (61m)	300ft (91m)	500ft (152m)	
1150 VA	3	100ft (30m)	150ft (46m)	250ft (76m)	
1500 VA	4	70ft (21m)	100ft (30m)	200ft (61m)	

GENERAL NOTES:

<u>NOTE:</u>

3 00

ON LAN.

• COMPLY WITH LOCAL BUILDING CODES.

1. CABINETS MAY BE MULTI-DROPPED

SIEMENS

- SIZE WIRE FOR LOAD, CURRENT, AND VOLTAGE.
- ALL WIRE TO BE APPROVED OR LISTED FOR THE INTENDED APPLICATION BY AGENCIES SUCH AS UL, (
- ALWAYS REFER TO LOCAL CODES FOR CONDUIT SHAF
- WIRING MUST HAVE INSULATION RATED FOR HIGHEST VOLTAGE CIRCUIT IN CONDUIT.
- PLENUM WIRING MAY BE USED IN PLACE OF ANY LOW VOLTAGE WIRING WITHOUT CHANGES TO LENGTH EXCE FOR PMD OR LAN TRUNK. IN CASES WHERE PLENUM (#18 OR #20 AWG) IS USED FOR PMD OR LAN TRUN USE THE REDUCED LENGTHS OF #20 AWG CABLE.
- THE LAN TRUNK MUST BE AN UNINTERRUPTED RUN BETWEEN CABINETS. NO SPLICES ALLOWED.

	24VAC (CLASS 2) OR DI, AI POINT WIRING	
4 Dft m) Ift m) Ift n)	"A" DENOTES 1/2"-3/4" CONDUIT KNOCKOUTS "B" DENOTES 1/2"-3/4" CONDUIT KNOCKOUTS	≥ ″₿″
CSA. .RING.	1 FLNC CONDUIT PENETRA	TION
)W EPT 1 WIRE NK,	FLNC POWER SOURCE REQUIREMENTS VOLTAGE: 115/230 VAC +10% -15% LINE FREQUENCY: 50 / 60 Hz POWER: 12 VA	
		S RE NUT YP)
SHLD TB-9	- COVER	0
	2 FLNC POWER WIRING) 20WER - 24
uite 24 Dianap	DODVIEW TRACE 40 POLIS, IN 46268 STATES BL065 OPTOMETRY S IU PROJECT #20241256 ENGINEER DRAFTER CHECKED E	3, IN

SIEMENS INDUSTRY INC. SMART INFRASTRUCTURE DIVISION

FLNC LAN TERMINATION


350 SU IND UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374

		20241256,	
ENGINEER	DRAFTER	CHECKED BY	INITI
HB	HB	CHECKED BY	0
FLNC	Termi	ination \$	Spe

© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED

REVISION HISTORY

00 5/9/2025 HB SUBMITTAL SET




DPU/MPU WIRING TYPE AND GAUGE REQUIREMENTS


IABLE I							
CIRCUIT TYPE	CLASS	WIRE TYPE	MAX. DISTANCE	CONDUIT SHARING			
AC LINE POWER (DPU)	1	#12-14 THHN	AS REQUIRED	CHECK LOCAL CODES			
POWER TRUNK ¹ (MPU)	2	#14 THNN OR #14 TP	180ft (55 m)	CLASS 1 & 2 CHECK CODES			
DIGITAL OUTPUT	1	CHECK LOCAL CODES	SEE TABLE 4	CHECK LOCAL CODES			
DIGITAL OUTPUT	2	CHECK LOCAL CODES	SEE TABLE 4	CHECK LOCAL CODES			
DIGITAL INPUT	2	#18-22 TP	750ft (230 m)	CLASS 1 & 2 CHECK LOCAL CODES			
ANALOG INPUT THERMISTOR	2	#18-22 TP	100ft (30.5 m)	CLASS 1 & 2 CHECK CODES			
LAN TRUNK ²	2	#18-22 AWG TSP	4kft (1220 m)	CLASS 2 ONLY			

FOR EACH TIE).


DI, AI, AO WIRE	SPECIFICATIONS
-----------------	----------------

SPECIFICATION	WIRE TYPE					
SPECIFICATION	SHIELDED	UNSHIELDED				
CAPACITANCE WIRE TO WIRE	NOT SPECIFIED	NOT SPECIFIED				
CAPACITANCE BETWEEN ONE CONDUCTOR WITH OTHER CONDUCTOR CONNECTED TO SHIELD	NOT SPECIFIED	N/A				
WIRE LAY	2" MAX.	2" MAX.				
AWG	18-22	18-22				





8D, 16D MAXIMUM PULSE RATE = 10Hz(50ms PER STATE, 100ms PER PULSE) 8U, 8X MAXIMUM PULSE RATE = 20Hz(25ms PER STATE, 50ms PER PULSE) PXC MODULAR DO CONTACT RATINGS AC OPERATION: 4A @ 240VAC (RESISTIVE) 3A @ 240VAC (INDUCTIVE) SIZE 4 MOTOR STARTER DC OPERATION: 40W @ < 50VDC20W @ > 50VDCREFER TO PXC MODULAR PANEL FOR ACTUAL POINT ADDRESSES. REFER TO TXMI TERMINATION TABLES FOR ACTUAL TERMINALS FOR EACH PANEL ADDRESS. COMMON TERMINAL MAY BE SHARED BY 2 POINTS. REFER TO DRAWING P1 ON TWIR FOR MAXIMUM CURRENT PROVIDED BY THE 24VDC SENSOR SUPPLY ON P1 BIM OR BUS POWER SUPPLY EXTERNAL POWER SUPPLY CAN EITHER BE A 24VDC POWER SUPPLY OR A 24VAC TRANSFORMER DEPENDING ON THE SENSOR SELECTED. IF NOT AN ISOLATED NC CLASS 2 CIRCUIT THEN POWER SOURCE, NEUTRAL AND PXC MODULAR COMMON MUST BE BOTH CONNECTED TO THE SAME OR BONDED BUILDING APPROVED EARTH GROUND. FOR FURTHER DETAILS SEE EARTH GROUNDING RULES (125-3002) APOGEE WIRING GUIDELINES FOR FIELD PANELS AND EQUIPMENT CONTROLLERS. 50mA OR LESS - 750ft/230m 50mA TO 100mA - 375ft/115m 100mA TO 150mA - 250ft/76m 150mA TO 200mA - 187ft/57m 200mA TO 250mA - 150ft/46m WHERE H TERMINAL IS NOT A NEC CLASS 2 CIRCUIT, RELAY COMMON TERMINAL BRANCH CURRENT MUST BE EXTERNALLY LIMITED TO 10A MAXIMUM BY AN NEC APPROVED MEANS. NOT A WHERE REQUIRED, N TERMINAL BRANCH CURRENT MUST BE EXTERNALLY LIMITED BY AN NEC APPROVED MEANS. 440P398851 Ω INITIAL RELEASE | LAST EDIT DATE 05/09/25 05/09/25



TXM1 TERMINATION TABLES

1. ALL TXM1 TERMINALS (MEASURING, NEUTRAL, RELAY, SUPPLY) ARE CONNECTED IN THE PLUG-IN I/O MODULE, NOT IN THE TERMINAL BUS.

			٦	XM1	.8D,	TXM	1.16[)	
I/O POINT		(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
SYSTEM NEUTRAL ¹	(-)	1	3	5	7	9	11	13	15
DIGITAL INPUT	(+)	2	4	6	8	10	12	14	16

1. NEUTRAL CAN BE CONNECTED TO ANY NEUTRAL TERMINAL ON SAME MODULE AND SEVERAL CAN SHARE SAME NEUTRAL TERMINAL.

				TXM1	.16D			
I/O POINT	(9)	(10)	(11)	(12)	(13)	(14)	(15)	(16)
SYSTEM NEUTRAL \perp (-)	18	20	22	24	26	28	30	32
DIGITAL INPUT 1 + (+)	19	21	23	25	27	29	31	33

DIGITAL INPUT	1 (+)	19		23	20	Ζ/	29	51	- 33
1. NO PULSE ACCUMULATOR									
			ΤX	M1.8	υ, τ	XM1.	8U-	ML	
I/O POINT		(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
SYSTEM NEUTRAL	⊥(-)	2	6	10	14	19	23	27	31
UNIVERSAL I/O	; (+)	4	8	12	16	21	25	29	33
24V AC/DC ACTUATOR SUPPL	$_{-Y^1}$ \sim		7		15		24		32

1. 24V DC ONLY AVAILABLE WITH BUS CONNECTOR MODULE (BCM) POWERED EXTERNALLY BY DC SUPPLY.

		TXM1.8X, TXM1.8X-ML						
I/O POINT	(1)	(2)	(3)	(4)	(5)	$(6)^{1}$	$(7)^{1}$	(8)
SYSTEM NEUTRAL \perp (-)	2	6	10	14	19	23	27	31
UNIVERSAL I/O (+)	4	8	12	16	21	25	29	33
24V AC/DC ACTUATOR SUPPLY2 \eqsim		7		15		24		32
24V DC SENSOR SUPPLY ³	3		11		20		28	

1. 4-20 mA OUTPUT AVAILABLE ON POINTS 5-8 ONLY.

2. 24V DC ONLY AVAILABLE WITH BUS CONNECTOR MODULE (BCM) POWERED EXTERNALLY BY DC SUPPLY.


3. MAY POWER EXTERNAL SENSORS 0.6w (25mA) OR 1.2w (50mA) PER TERMINATION UP TO 2.4w (100mA) MAXIMUM FOR ALL TERMINATIONS.

			T>	KM1.6	SR, ⁻	TXM1	.6R-	М
I/O POINT			(1)	(2)	(3)	(4)	(5)	(6
COMMON 1	t	(C)	3	9	15	20	26	32
NORMALLY CLOSED	A	(NC)	4	10	16	19	25	31
NORMALLY OPEN	ł	(NO)	2	8	14	21	27	33

1. COMMONS ARE NOT INTERNALLY CONNECTED.


NOTE: REFER TO TERMINATION SHEET #1 FOR INSTALLATION DETAILS.

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240	BL065 OPTOMETRY SCH-LAB RENO
00 5/9/2025 HB SUBMITTAL SET		INDIANAPOLIS, IN 46268	IU PROJECT #20241256, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL RELEASE HB HB 05/09/25 05/09/25 05/09/25 05/09/25
	SMART INFRASTRUCTURE DIVISION		TX-I/O Termination Spec. 2
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED			




440P398851 0






_AB RENO)	44OP398851 0
ITIAL RELEASE D5/09/25	LAST EDIT DATE 05/09/25	TTRM
Spec. 3		



INSTALLATION NOTES:

TRANSFORMER PANELS TO BE LOCATED AS SHOWN ON ELECTRICAL DRAWINGS. MOUNTING AND FIELD WRING BY CIC, POWER WRING BY EC.



© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED


-LAB RENO	
N	
INITIAL RELEASE 05/09/25	LAST EDIT DATE 05/09/25

^{440P398851} 0

Contro Device		Qty	Product Number		Document Number	Description
Field	Mounted Devices					
PWR	4A	1	PSH500A-LVC	FUNCTIONAL		Power Supply HILO 100VAx5 multi-tap
PWR	4B	1	PSH500A-LVC	FUNCTIONAL		Power Supply HILO 100VAx5 multi-tap

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE	BL065 OPTOMETRY SCH-LAB RENO
DO 5/9/2025 HB SUBMITTAL SET	SIEMENS INDUSTRY INC.	SUITE 240 INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880 FAX: 317-293-0374	IU PROJECT #20241256, IN ENGINEER DRAFTER CHECKED BY INITIAL RELEASE HB HB 05/09/25 05/09/25
Copyright 1994-2025 Siemens industry Inc. All rights reserved	SMART INFRASTRUCTURE DIVISION		POWER TRUNK BOM


440P398851 0 R02A




[©] COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED

ELECTRICAL DRAWING ON SUBSEQUENT SHEET.
F ACTUATOR ENDSWITCH REQUIRED.
ELECTRICAL DRAWING ON SUBSEQUENT SHEET.
AND SENSOR IN THE FIFTH FLOOR DUCTWORK. 10 SPACE.
ORS WITH ENDSWITCHES PROVIDED HERS.
TALLED BY OTHERS.

AB RENO		44
TIAL RELEASE 5/09/25	LAST EDIT DATE 05/09/25	4



SCH-LAB RENO 56, IN BY INITAL RELEASE LAST EDIT DATE 05/09/25 05/09/25 RING		
440P398851		DRAWING NOTES: # 1. LOCATE RELAY ADJACENT TO ITS ASSOCIATED VARIABLE FROURCY DRIVE OR STARTER. 2. VERIFY VFD CABLE SPECIFICATIONS AND INPUT ISOLATION REQUIREMENTS WITH VFD MANUFACTURER. GENERAL NOTES: 1. ALL WRING TO MEET REQUIREMENTS OF STANDARD WRING SPECIFICATIONS DRAWINGS. 2. 120VAC POWER BY ELECTRICAL CONTRACTOR. 3. EXACT LOCATIONS OF FIELD DEVICES TO BE COORDINATED WITH IUPUI/SIEMENS.




Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field Mounted Devices						
AE	1	1	FBO			FURNISHED BY OTHERS
DPTE	1	1	2641005WB11A1C	SETRA	0608cut003	DP TRAN AIR,1%,+/-5" ENC
RIB	1	1	RIBU1C	FUNCTIONAL DEVICES	1208cut013	RIB 120VAC 24VAC/DC SPDT
SPP	1	1	A-489	DWYER INST	A(PRS TIP)	4" straight static pressure tip w/flange
SPP	2	1	RPS-W	KELE		WHITE PLASTIC ROOM PRESSURE SENSOR
VFD	1	1	FBO			FURNISHED BY OTHERS
Panel Mounted Devices						
RE	5	1	RH2B-UL-AC24VKIT	IDEC	1202cut016	RELAY&SOC,GP DPDT AC24V W/LED
RE	6	1	RH2B-UL-AC24VKIT	IDEC	1202cut016	RELAY&SOC,GP DPDT AC24V W/LED

EXHAUST FAN CONTROL:


LEF-3 OPERATES CONTINUOUSLY. THE VARIABLE FREQUENCY CONTROLER SHALL MODULATE FAN SPEED TO MAINTAIN DUCT STATIC PRESSURE SETPOINT OF -1.0" wg (ADJ). DUCT STATIC PRESSURE SHALL BE DETERMINED AT TIME OF SYSTEM BALANCING.

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240	BL065 OPTOMETRY SCH-LAB RENO		
00 5/9/2025 HB SUBMITTAL SET	SIEMENS INDUSTRY INC.	INDIANAPOLIS, IN 46268 UNITED STATES PHONE: 317-293-8880	IU PROJECT #20241256, IN ENGINEER DRAFTER CHECKED BY INITIAL RELEASE LAST EDIT DATE HB HB 05/09/25 05/09/25		
SMART INFRASTRUCTURE		FAX: 317-293-0374	LEF-3 CONTROL BOM & SOO		
© Copyright 1994-2025 Siemens industry Inc. All rights reserved					

440P398851 0 **100C**



AB RENO		440P398 0
	ST EDIT DATE 05/09/25	10
CM		ΗV



). WIRING	W-LCM ELEC.	S
	05/09/25	05/09/25	
	LAST EDIT DATE	INITIAL RELEASE	B
0		56, IN	56
440P398851		SCH-LAB RENO	SC

EQUIPMENT TO BE POWERED	PWR TRUNK 1	PWR TRUNK 2	PWR TRUNK 3	MAX RATING
LCM-1	Х			7 VA
SUPPLY AIR BOX ACTUATOR GDE	Х			2.3 VA
SUPPLY AIR OFF-BOARD MODULE	Х			~7 VA
0-10 VDC REHEAT VALVE	Х			3.5 VA
EXHAUST AIR BOX ACTUATOR GDE	Х			2.3 VA
EXHAUST AIR OFF-BOARD MODULE	Х			~7 VA
T-STAT QAA	Х			2.0 VA

TOTAL: 31.1 VA

INSTALLATION NOTES:	
ALL WRING TO MEET REQUIREMENTS OF STA	NDARD
IF NO FUME HOOD(S) INPUT WILL BE CONNE AI3, MAKE SURE MAX HOOD VOL = 0 (DEF.	CTED TO

Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field Mc	ounted Devices	3				
AE	1-2	8	GDE131.1P	SIEMENS	154 011	ACT NSR PLENUM 24/108L 5Nm
CBL	1	4	588-100B	SIEMENS		6-WIRE 2-RJ11 RS CABLE 50'PLMN
LCM	1	4	550-767FN	SIEMENS	149856	LCM-OAVS DAMPER SLOW SPEED
OAM	1-2	8	550-819B	SIEMENS		REMOTE AIR MODULE, PTEC
TTE	1	4	QAA2280.FWSC	SIEMENS	149820	RTS, TEC/RJ-11, FULL HMI
TTE	2	4	536-811	SIEMENS	149 134	DCT PT TMP, 100K OHM, 4", BRACKET MNT

LABORATORY AIRFLOW SEQUENCE OF OPERATION

A. GENERAL

1. CONTROL OF AIRFLOW TO AN FROM EACH LABORATORY SPACE AND CONTROL OF SPACE TERMPERATURE WITHIN THE LABORATORY SPACE SHALL BE ACCOMPLISHED BY THE LABORATORY AIRFLOW CONTROL SYSTEM (LACS). THE LACS SHALL UTILIZE DDC MICROPROCESSOR BASED LOGIC TO ACHEIVE ALL CONTROL FUNCTIONS.

B. AIRFLOW CONTROL


1. SUPPLY AIR TERMINAL UNIT WITH REHEAT (SAV-XXX): MODULATE SUPPLY TERMINAL UNIT DAMPER TO MAINTAIN OFFSET WITH EXHAUST AIRFLOW. MODULATE HEATING COIL TEMPERATURE CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE SETPOINT.

2. EXHAUST VALVE (EAV-XXX): MODULATE EXHAUST AIR VALVE TO MAINTAIN MAXIMUM EXHAUST WHEN LABORATORY IS OCCUPIED.

GRAPHICALLY DISPLAY THE FOLLOWING POINTS, AT A MINIMUM, AT THE OPERATOR WORKSTATION:


ANALOG INPUTS SPACE TEMPERATURE (ZN-T) AIR VALVE POSITION AS A PERCENT OPEN (DPR-O) TEMPERATURE CONTROL VALVE POSITION AS A PERCENT OPEN (RH-VLV) EXHAUST AIRFLOW VALUE FOR EXHAUST VALVES AND EXHAUST TERMINAL UNITS (EXH-CFM) SUPPLY AIRFLOW VALUE FOR SUPPLY TERMINAL UNITS (SA-CFM) DISCHARGE AIR TEMPERATURE FOR SUPPLY TERMINAL UNITS (DA-T)


REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268	BL065 OPTOMETRY SCH-LAB RENO IU PROJECT #20241256, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL RELEASE HB HB 05/09/25 05/09/25 05/09/25 05/09/25
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	ISAV-1EAV-SLOW-LCM BOM
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED			



440P398851 0 400B

	5 OPTOMETRY SCH-L OJECT #20241256, IN R DRAFTER CHECKED BY INIT HB 0
EXISTING TO REMAIN OAM-1	
EXISTING TO REMAIN OAM-1 OAM-1 OAM-1 OAM-1 OAM-1 OAM-1 OAM-1 OUT <u>3C A1</u> <u>3C D1</u> <u>2C D1</u> <u>2C D1</u> <u>2C C1</u> <u>2C C1</u> <u>C1</u> <u>C1</u> <u>C1</u> <u>C1</u> <u>C1</u> <u>C1</u> <u>C1</u> <u></u>	
$\begin{array}{c} 1 \\ \hline \\$	I EAV-406 F
7 DUCT DAMETER DUCT DAMETER 2 REPLACE THE I 3 REFER TO BUIL 4 SEE ASSOCIATE 5 DEMO THE EXIS 1 NSTALL NEW 6 REPLACE THE E 6 REPLACE THE E 7	SE ALLED BY MECHANICAL CO RS UPSTREAM OF BOX TO EXISTING TEC WITH LCM, WE OWNER.CIC FIELD MOUN DING POWER TRUNK DRAY ED WRING DIAGRAM FOR STING T-STAT AND ASSO T-STAT AND CABLE, LOC EXISTING SA DUCT TEMPE EXISTING WRE WHERE APF EXISTING VALVE ACTUATO DY STAYED IN PLACE. RE





		. WIRING	EC.
	05/09/25	05/09/25	
	LAST EDIT DATE	D BY I INITIAL RELEASE	D BY
0		Z	56, IN
440P398851		SCH-LAB RENO	SCF

EQUIPMENT TO BE POWERED	PWR TRUNK 1	PWR TRUNK 2	PWR TRUNK 3	MAX RATING
LCM-1	X			7 VA
SUPPLY AIR BOX ACTUATOR GDE	Х			2.3 VA
SUPPLY AIR OFF-BOARD MODULE	Х			~7 VA
0-10 VDC REHEAT VALVE	Х			3.5 VA
EXHAUST AIR BOX ACTUATOR GDE	Х			2.3 VA
EXHAUST AIR OFF-BOARD MODULE	X			~7 VA
T-STAT QAA	X			2.0 VA

TOTAL: 31.1 VA

INSTALLAT	ION NOTES:	_	
1 ALL WRI	NG TO MEET RE PECIFICATIONS	QUIREMENTS DRAWINGS	OF STANDARD
2 IF NO FI AI3, MAI	IME HOOD(S) IN E SURE MAX H	IPUT WILL BE	CONNECTED T

Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field N	lounted Devices	3		I		
AE	1	1	EXISTING TO REMAIN			
AE	2	1	GDE131.1P	SIEMENS	154 011	ACT NSR PLENUM 24/108L 5Nm
CBL	1	1	588-100A	SIEMENS		6-WIRE 2-RJ11 RS CABLE 25'PLMN
LCM	1	1	550–767FN	SIEMENS	149856	LCM-OAVS DAMPER SLOW SPEED
OAM	1-2	2	550-819B	SIEMENS		REMOTE AIR MODULE, PTEC
TTE	1	1	QAA2280.FWSC	SIEMENS	149820	RTS, TEC/RJ-11, FULL HMI
TTE	2	1	536-811	SIEMENS	149 134	DCT PT TMP, 100K OHM, 4", BRACKET MNT
V*	1	1	SSC161.05U	SIEMENS		MODULATING VALVE ACTUATOR 0-10VDC

MODIFY CONTROL SEQUENCE AS REQUIRED TO MEET THE FOLLOWING SEQUENCE OF OPERATION.

LABORATORY AIRFLOW SEQUENCE OF OPERATION

A. GENERAL

1. CONTROL OF AIRFLOW TO AN FROM EACH LABORATORY SPACE AND CONTROL OF SPACE TERMPERATURE WITHIN THE LABORATORY SPACE SHALL BE ACCOMPLISHED BY THE LABORATORY AIRFLOW CONTROL SYSTEM (LACS). THE LACS SHALL UTILIZE DDC MICROPROCESSOR BASED LOGIC TO ACHEIVE ALL CONTROL FUNCTIONS.

B. AIRFLOW CONTROL

1. SUPPLY AIR TERMINAL UNIT WITH REHEAT (SAV-XXX): MODULATE SUPPLY TERMINAL UNIT DAMPER TO MAINTAIN OFFSET WITH EXHAUST AIRFLOW. MODULATE HEATING COIL TEMPERATURE CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE SETPOINT.


2. EXHAUST VALVE (EAV-XXX): MODULATE EXHAUST AIR VALVE TO MAINTAIN MAXIMUM EXHAUST WHEN LABORATORY IS OCCUPIED.

GRAPHICALLY DISPLAY THE FOLLOWING POINTS, AT A MINIMUM, AT THE OPERATOR WORKSTATION:


ANALOG INPUTS SPACE TEMPERATURE (ZN-T) AIR VALVE POSITION AS A PERCENT OPEN (DPR-O) TEMPERATURE CONTROL VALVE POSITION AS A PERCENT OPEN (RH-VLV) EXHAUST AIRFLOW VALUE FOR EXHAUST VALVES AND EXHAUST TERMINAL UNITS (EXH-CFM) SUPPLY AIRFLOW VALUE FOR SUPPLY TERMINAL UNITS (SA-CFM) DISCHARGE AIR TEMPERATURE FOR SUPPLY TERMINAL UNITS (DA-T)

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE	BL065 OPTOMETRY SCH-LAB RENO
00 5/9/2025 HB SUBMITTAL SET		SUITE 240 INDIANAPOLIS, IN 46268	IU PROJECT #20241256, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL RELEASE LAST EDIT Date HB HB 05/09/25 05/09/25 05/09/25 05/09/25
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	LAB RM 406 CTRL BOM & SOO
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED			

440P398851 0 401B



AB RENO	440P398851 0
nal release last edit date 5/09/25 05/09/25	410



	WIRING	F-LCM ELEC. WIRING
	LAST EDIT DATE 05/09/25	BY INITIAL RELEASE I 05/09/25
0		56, IN
440P398851		SCH-LAB RENO

EQUIPM	ENT TO BE POWERED	PWR TRUNK 1	PWR TRUNK 2	PWR TRUNK 3	MAX RATING
LCM-1		X			7 VA
SUPPLY AIR	BOX ACTUATOR GNP	Х			28.0 VA
SUPPLY AIR	OFF-BOARD MODULE	X			~7 VA
0-10 VDC R	EHEAT VALVE	Х			3.5 VA
EXHAUST AIR	BOX ACTUATOR GNP	X			28.0 VA
EXHAUST AIR	R OFF-BOARD MODULE	X			~7 VA
T-STAT QAA		X			2.0 VA

TOTAL: 73.1 VA

1 (410A) LAB RM CNTRL-WIRING DIAGRAM INSTALLATION NOTES: ALL WRING TO MEET REQUIREMENTS OF STANDARD WRING SPECIFICATIONS DRAWINGS 2 FLOW SIGNAL FROM (1) FHC OR FFM IF REQUIRED.

Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field M	ounted Device	s				
AE	1-2	2	GNP191.1P	SIEMENS	154083	FAIL SAFE, 50 LB-IN, 2 SEC. RUN
CBL	1	1	588-100B	SIEMENS		6-WIRE 2-RJ11 RS CABLE 50'PLMN
LCM	1	1	550-767EN	SIEMENS	149856	LCM – OAVS, DAMPER FAST/RTS&BTU
OAM	1-2	2	550-819B	SIEMENS		REMOTE AIR MODULE, PTEC
TTE	1	1	QAA2280.FWSC	SIEMENS	149820	RTS, TEC/RJ-11, FULL HMI
TTE	2	1	536-811	SIEMENS	149 134	DCT PT TMP, 100K OHM, 4", BRACKET MNT

LABORATORY AIRFLOW SEQUENCE OF OPERATION

A. GENERAL

1. CONTROL OF AIRFLOW TO AN FROM EACH LABORATORY SPACE AND CONTROL OF SPACE TEMPERATURE WITHIN THE LABORATORY SPACE SHALL BE ACCOMPLISHED BY THE LABORATORY AIRFLOW CONTROL SYSTEM (LACS). THE LACS SHALL UTILIZE DDC

MICROPROCESSOR BASED LOGIC TO ACHEIVE ALL CONTROL FUNCTIONS.

2. OPERATE EXHAUST VALVE TO MAINTAIN REQUIRED DESIGN AIRFLOW RATE FOR EACH FUMEHOOD WITH SASH OPEN AND MINIMUM REQUIRED AIRFOW FOR EACH FUMEHOOD WITH SASH CLOSED.

B. AIRFLOW CONTROL

1. SUPPLY AIR TERMINAL UNIT WITH REHEAT (SAV-401): MODULATE SUPPLY TERMINAL UNIT DAMPER TO MAINTAIN OFFSET WITH EXHAUST AIRFLOW. MODULATE HEATING COIL TEMPERATURE CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE SETPOINT.


2. FUME HOOD EXHAUST VALVE (HEV-401): MODULATE EXHAUST AIR VALVE TO MAINTAIN 80 FPM WHEN LABORATORY IS OCCUPIED.

3. GENERAL EXHAUST VALVE (EAV-401): MODULATE GENERAL EXHAUST TERMINAL UNIT DAMPER TO MAINTAIN TOTAL EXHAUST AIRFLOW (FUME HOODS, & GENERAL EXHAUST VALVE) AT 6 AC/HR CONTINUOUSLY (24/7). GENERAL EXHAUST IS THE DIFFERENCE BETWEEN THE TOTAL REQUIRED EXHAUST AIRFLOW FOR THE SPACE AND THE EXHAUST AIRFLOW FROM FUME HOOD AND IN THE LABORATORY SPACE.


GRAPHICALLY DISPLAY THE FOLLOWING POINTS, AT A MINIMUM, AT THE OPERATOR WORKSTATION:


ANALOG INPUTS SPACE TEMPERATURE (ZN-T) AIR VALVE POSITION AS A PERCENT OPEN (DPR-O) TEMPERATURE CONTROL VALVE POSITION AS A PERCENT OPEN (RH-VLV) EXHAUST AIRFLOW VALUE FOR EXHAUST VALVES AND EXHAUST TERMINAL UNITS (EXH-CFM) SUPPLY AIRFLOW VALUE FOR SUPPLY TERMINAL UNITS (SA-CFM) DISCHARGE AIR TEMPERATURE FOR SUPPLY TERMINAL UNITS (DA-T)

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240			-	H-LAB RENO	
00 5/9/2025 HB SUBMITTAL SET		INDIANAPOLIS, IN 46268	IU PROJECT #20241256, IN				
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER HB	DRAFTER HB	CHECKED BY	INITIAL RELEASE	
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	1SAV	-1EAV	-FAST-	LCM BOM	



440P398851 0 410B






REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE	BL065 OPTOMETRY SCH-LAB RENO				
00 5/9/2025 HB SUBMITTAL SET		SUITE 240 INDIANAPOLIS, IN 46268	IU PROJECT #20241256, IN				
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL RELEASE LAST EDIT DATE HB HB 05/09/25 05/09/25 05/09/25				
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	FUME HOOD CONTROL				
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED							

> FHC−1 IS FACTORY MOUNTED IN MANUFACTURER SUPPLIED CONTROLLER


440P398851 0



		-EC. WIRING	Ē
	05/09/25	05/09/25	
	LAST EDIT DATE	INITIAL RELEASE	BΥ
0		Z	56, IN
440P398851		SCH-LAB RENO	SC

EQUIPMENT TO BE POWERED	PWR TRUNK 1	PWR TRUNK 2	PWR TRUNK 3	MAX RATING
FHC-1	Х			7 VA
EXHAUST AIR BOX ACTUATOR GNP	X			28.0 VA
SUPPLY AIR OFF-BOARD MODULE	X			~7 VA
FH OPERATOR	X			2.0 VA

TOTAL: 44.0 VA



INSTALLATION NOTES:

1 ALL WRING TO MEETREQUIREMENTS OF STANDARD WRING SPECIFICATIONS DRAWINGS

2 FLOW SIGNAL TO LAB ROOM CONTROLLER LCM.

Control Device		Qty	Product Number	Manufacturer	Document Number	Description
Field Mo	ounted Devices	1	-			
AE	1	1	PART OF LGE-1			LAB CONTROLS
FHC	1	1	PART OF LGE-1			LAB CONTROLS
OAM	1	1	PART OF LGE-1			LAB CONTROLS
ODP	1	1	575-820A	SIEMENS		FUME HOOD OPERATOR DISPLAY PANEL PTEC
		1	AQM2200	SIEMENS		POWER MODULE
PSE	1	1	546-00488	SIEMENS	149269	VERT UNI-TRAK TOP ASSY,35"

LABORATORY AIRFLOW SEQUENCE OF OPERATION

A. GENERAL

1. CONTROL OF AIRFLOW TO AN FROM EACH LABORATORY SPACE AND CONTROL OF SPACE TEMPERATURE WITHIN THE LABORATORY SPACE SHALL BE ACCOMPLISHED BY THE LABORATORY AIRFLOW CONTROL SYSTEM (LACS). THE LACS SHALL UTILIZE DDC

MICROPROCESSOR BASED LOGIC TO ACHEIVE ALL CONTROL FUNCTIONS.

2. OPERATE EXHAUST VALVE TO MAINTAIN REQUIRED DESIGN AIRFLOW RATE FOR EACH FUMEHOOD WITH SASH OPEN AND MINIMUM REQUIRED AIRFOW FOR EACH FUMEHOOD WITH SASH CLOSED.

B. AIRFLOW CONTROL

1. SUPPLY AIR TERMINAL UNIT WITH REHEAT (SAV-401): MODULATE SUPPLY TERMINAL UNIT DAMPER TO MAINTAIN OFFSET WITH EXHAUST AIRFLOW. MODULATE HEATING COIL TEMPERATURE CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE SETPOINT.

2. FUME HOOD EXHAUST VALVE (HEV-401): MODULATE EXHAUST AIR VALVE TO MAINTAIN 80 FPM WHEN LABORATORY IS OCCUPIED.


3. GENERAL EXHAUST VALVE (EAV-401): MODULATE GENERAL EXHAUST TERMINAL UNIT DAMPER TO MAINTAIN TOTAL EXHAUST AIRFLOW (FUME HOODS, & GENERAL EXHAUST VALVE) AT 6 AC/HR CONTINUOUSLY (24/7). GENERAL EXHAUST IS THE DIFFERENCE BETWEEN THE TOTAL REQUIRED EXHAUST AIRFLOW FOR THE SPACE AND THE EXHAUST AIRFLOW FROM FUME HOOD AND IN THE LABORATORY SPACE.

GRAPHICALLY DISPLAY THE FOLLOWING POINTS, AT A MINIMUM, AT THE OPERATOR WORKSTATION:

ANALOG INPUTS SPACE TEMPERATURE (ZN-T) AIR VALVE POSITION AS A PERCENT OPEN (DPR-O) TEMPERATURE CONTROL VALVE POSITION AS A PERCENT OPEN (RH-VLV) EXHAUST AIRFLOW VALUE FOR EXHAUST VALVES AND EXHAUST TERMINAL UNITS (EXH-CFM) SUPPLY AIRFLOW VALUE FOR SUPPLY TERMINAL UNITS (SA-CFM) DISCHARGE AIR TEMPERATURE FOR SUPPLY TERMINAL UNITS (DA-T)

REVISION HISTORY	SIEMENS	3502 WOODVIEW TRACE SUITE 240	BL065 OPTOMETRY SCH-LAB RENO				
00 5/9/2025 HB SUBMITTAL SET		INDIANAPOLIS, IN 46268 UNITED STATES			20241256,	IN INITIAL RELEASE	LAST EDIT DATE
	SIEMENS INDUSTRY INC.	PHONE: 317-293-8880	HB	HB		05/09/25	05/09/25
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	FH C	ONTR	OL BOM	1 & SOO	





AB	RENO

440P398851 0


Control Device			Description			
Field Mc	ounted Devices					
AE	1	2	GDE131.1P	SIEMENS	154 011	ACT NSR PLENUM 24/108L 5Nm
CBL	1	2	588-100A	SIEMENS		6-WIRE 2-RJ11 RS CABLE 25'PLMN
TEC	1	2	540-100N	SIEMENS	1491014	TERM BOX CTLR ELEC OUT
TTE	1	2	QAA2280.FWSC	SIEMENS	149820	RTS, TEC/RJ-11, FULL HMI
TTE	2	2	536-811	SIEMENS	149 134	DCT PT TMP, 100K OHM, 4", BRACKET MNT

VAV BOX WITH REHEAT SEQUENCE OF OPERATION


DISCHARGE AIR TEMPERATURE SENSOR: TCC SHALL PROVIDE A SUPPLY AIR TEMPERATURE SENSOR (SA-T) FOR MONITORING PURPOSES.

OCCUPIED MODE: WHEN THE ZONE TEMPERATURE (ZN-T) IS BETWEEN THE HEATING AND COOLING SETPOINTS, THE PRIMARY AIR DAMPER (DPR-O) WILL BE AT THE MINIMUM CFM (SA-CFM) AND THE REHEAT VALVE (RH-VLV) SHALL BE FULLY CLOSED. ON A RISE IN ZONE TEMPERATURE ABOVE THE COOLING SETPOINT, THE PRIMARY AIR DAMPER SHALL INCREASE THE CFM AND THE REHEAT VALVE SHALL REMAIN FULLY CLOSED. ON A DROP IN TEMPERATURE BELOW THE HEATING SETPOINT, THE REHEAT VALVE SHALL MODULATE OPEN AND THE PRIMARY AIR DAMPER SHALL MAINTAIN MINIMUM CFM. SPACE SENSORS SHALL HAVE SETPOINT ADJUSTMENT AND UNOCCUPIED CYCLE OVERRIDE (SOFTWARE SELECTABLE AS DETERMINED BY THE OWNER).


REVISION HISTORY 00 5/9/2025 HB SUBMITTAL SET	SIEMENS	3502 WOODVIEW TRACE SUITE 240 INDIANAPOLIS, IN 46268	BL065 OPTOMETRY SCH-LAB RENO IU PROJECT #20241256, IN
	SIEMENS INDUSTRY INC.	UNITED STATES PHONE: 317-293-8880	ENGINEER DRAFTER CHECKED BY INITIAL RELEASE HB HB 05/09/25 05/09/25 05/09/25 05/09/25
	SMART INFRASTRUCTURE DIVISION	FAX: 317-293-0374	VAV w/HW REHEAT BOM &
© COPYRIGHT 1994-2025 SIEMENS INDUSTRY INC. ALL RIGHTS RESERVED			








SCH-LAB RENO 56, IN BY INITAL RELEASE LAST EDIT DATE 05/09/25 05/09/25	
440P398851 900	






SCH-LAB RENO 56, IN BY INITIAL RELEASE LAST EDIT DATE 05/09/25 05/09/25 3 Node 3p003		
440P398851 900B		

HEET PRINTED: 5/12/2025 12:31:48 PM







	A. DARK DASHED LINES INDICATE EXISTING MECHANICAL EQUIPMENT, DUCTWORK, PIPING, AND/OR MECHANICAL ACCESSORIES DEMOLISHED COMPLETE. CONTRACTOR TO FIELD VERIFY ACTUAL EXISTING CONDITIONS PRIOR TO BIDDING AND DEMOLITION. CONTRACTOR TO INCLUDE ALL COST TO REMOVE ITEMS MADE OBSOLETE DUE TO NEW HVAC WORK.	
	B. LIGHT SOLID LINES INDICATE EXISTING MECHANICAL EQUIPMENT, DUCTWORK, PIPING, AND/OR MECHANICAL ACCESSORIES TO REMAIN AS-IS. CONTRACTOR TO FIELD VERIFY ACTUAL EXISTING CONDITIONS PRIOR TO DEMOLITION AND BIDDING.	
	C. REMOVE ALL ABANDONED DUCT, INCLUDING ALL ASSOCIATED HANGERS, SUPPORTS, AND INSULATION ABOVE ALL CEILING IN LAB 407, LAB 407A, LAB407D, AND ALL SUPPORTED SPACES.	
[1
\bigwedge	OEMOLITION HVAC PLAN NOTES	
	1 REMOVE DUCT COMPLETE UP THROUGH ROOF. REMOVE EXHAUST FAN ON ROOF. PROVIDE ROOF	I
Y	2 REMOVE SPACE TEMPERATURE SENSOR COMPLETE.	I
ر ر	-3 - DIFEUSERS, DUCT, AND VAV TERMINAL UNIT LOCATED IN LAB 406 REMAIN.	I
	4 DIFFUSERS AND DUCT IN ROOM 404 REMAIN.	I
	5 DISCONNECT HWS/R PIPING FROM DUCT REHEAT COIL AND REMOVE BACK TO MAIN. REMOVE DUCT REHEAT COIL AND A PORTION OF DUCT IN ROOM 402 TO POINT INDICATED. PREPARE REMAINING DUCT AND HWS/R PIPING FOR CONNECTION TO NEW.	
	6 REMOVE TRANSFER GRILLE AND DUCT COMPLETE.	I
	7 DISCONNECT HWS/R PIPING FROM DUCT REHEAT COIL AND REMOVE BACK TO MAIN. REMOVE DUCT REHEAT COIL AND A PORTION OF DUCT IN ROOM 402 TO POINT INDICATED. PREPARE REMAINING DUCT AND HWS/R PIPING FOR CONNECTION OF NEW.	
	8 DIFFUSERS AND DUCT IN ROOM 402 AND ROOM 402A REMAIN.	I
	9 REMOVE SPACE TEMPERATURE SENSOR AND ASSOCIATED WIRING/PNEUMATIC TUBING BACK TO SOURCE.	
	10 DISCONNECT HWS/R PIPING FROM DUCT REHEAT COIL. REMOVE PIPE BACK TO MAIN. REMOVE DUCT REHEAT COIL COMPLETE.	
	11 REMOVE EXHAUST DUCT AND ASSOCIATED GRILLES, SUPPORT, AND HANGERS COMPLETE BACK TO RISER.	
	12 REMOVE ABANDONED 12x12 EXHAUST DUCT AND ASSOCIATED HANGERS AND SUPPORTS COMPLETE	·
	13 DISCONNECT 12x12 DUCT FROM FUME HOOD AND REMOVE TO POINT INDICATED. PREPARE REMAINING DUCT FOR CONNECTION OF NEW.	
	14 REMOVE DUCT COMPLETE UP THROUGH ROOF. REMOVE EXHAUST FAN ON ROOF. PROVIDE ROOF CURB CAP PER DETAIL '3/M601'.	
	15 ALL DUCT, PIPING, INSULATION, AND TERMINAL UNITS SERVING LAB 411 AND ALL SUPPORT SPACES REMAIN.	
	16 DISCONNECT HWS/R PIPING FROM VAV TERMINAL UNIT HEATING COIL. REMOVE VAV TERMINAL UNIT COMPLETE.	
$\underline{\land}$	17 REMOVE SUPPLY DUCT IN CORRIDOR AND ALL ASSOCIATED HANGERS, SUPPORTS AND INSULATION COMPLETE.	
\sim	18 REMOVE ADANDONED 12x8 DUCT AND ASSOCIATED HANGERS AND SUPPORTS COMPLETE.	
→ →	19 REMOVE ABANDONED 12x6 DUCT TO JUST BELOW FLOOR ABOVE AND CAP. SEAL AIR TIGHT.	
(I		

GENERAL DEMOLITION NOTES




INDIANA UNIVERSITY

IU20241256 BL065 OPTOMETRY SCHOOL - LAB RENOVATION ROOMS 401, 406 & 407

ARCHITECT DELV Design 212 W 10th St, STE F125 Indianapolis, IN 46202 (317) 296-7400

MEP





No.	Description	Date
1	Addendum #01	05.13.2025


CLIENT PROJ. #: IU20241256 PROJECT #: 24-065 ISSUE DATE: 05/01/2025 DRW: MP | CHK: JR

MECHANICAL DEMOLITION FOURTH FLOOR PLAN



HEET PRINTED: 5/12/2025 12:31:50 PM





GENERAL HVAC NOTES

- A. DARK LINES INDICATE NEW WORK.
- B. LIGHT SOLID LINES INDICATE EXISTING MECHANICAL EQUIPMENT, DUCTWORK, PIPING, AND/OR MECHANICAL ACCESSORIES TO REMAIN AS-IS. CONTRACTOR TO FIELD VERIFY ACTUAL EXISTING CONDITIONS PRIOR TO BIDDING.
- . REFERENCE M701 FOR REBALANCING OF EXISTING DUCT SYSTEMS CONNECTED TO AND EFFECTED BY THE NEW WORK.

MECHANICAL HVAC PLAN NOTES

- 12" EA DOWN TO FUME HOOD. PROVIDE TRANSITION TO HOOD CONNECTION AS REQUIRED.
 2 CONNECT VAV-402 INTO EXISTING 20x12 SA DUCT.
- 2 CONNECT VAV-402 INTO EXISTING 20X12 SA DUCT. 3 CONNECT VAV-404 INTO EXISTING 14x8 SA DUCT.
- CONNECT 8" SA TO EXISTING CAV-406.
 22x18 EA UP THROUGH ROOF AND TRANSITION TO LEF-3.
- 6 PROVIDE STAINLESS STEEL DUCT.
- 7 PROVIDE STAINLESS STEEL FILTER FRAME AND 2" MERV 8 FILTER. PROVIDE FILTER ACCESS DOOR C SIDE OF DUCT FOR FILTER REMOVAL AND INSTALLATION.




INDIANA UNIVERSITY

IU20241256 BL065 OPTOMETRY SCHOOL - LAB RENOVATION ROOMS 401, 406 & 407

ARCHITECT DELV Design 212 W 10th St, STE F125 Indianapolis, IN 46202 (317) 296-7400

MEP






No.	Description	Date
1	Addendum #01	05.13.2025

CLIENT PROJ. #: IU20241256 PROJECT #: 24-065 ISSUE DATE: 05/01/2025 DRW: MP | CHK: JR

MECHANICAL HVAC FOURTH FLOOR PLAN MH101

HEET PRINTED: 5/12/2025 12:31:51 PM





GENERAL PIPING NOTES

- A. DARK LINES INDICATE NEW WORK.
- B. LIGHT SOLID LINES INDICATE EXISTING MECHANICAL EQUIPMENT, DUCTWORK, PIPING, AND/OR MECHANICAL ACCESSORIES TO REMAIN AS-IS. CONTRACTOR TO FIELD VERIFY ACTUAL EXISTING CONDITIONS PRIOR TO BIDDING.
- . PROVIDE SHUTOFF VALVES AT EVERY BRANCH CONNECTION TO A MAIN.
- D. REFER TO DETAIL '2/M501' FOR TERMINAL UNIT PIPING.

O MECHANICAL PIPING PLAN NOTES CONNECT 3/4"HWS/R PIPING TO EXISTING TAPS.

- CONNECT 3/4"HWS/R PIPING TO EXISTING TAPS.
 CONNECT 3/4"HWS PIPING TO EXISTING TAP.
- 3 PROVIDE SHUT-OFF VALVE AND CAP 4 NEW HEATING WATER TEMPERATURE CONTROL VALVE ACTUATOR FURNISHED BY SIEMENS AND

1-

 INEW REATING WATER TEMPERATURE CONTROL VALVE ACTUATOR FURNISHED BY SIEMENS AND INSTALLED BY CIC.
 NEW TEMPERATURE SENSOR FURNISHED BY SIEMENS INSTALLED BY CIC.

1 MECHANICAL PIPNG FOURTH FLOOR PLAN 3/16" = 1'-0"




INDIANA UNIVERSITY

IU20241256 BL065 OPTOMETRY SCHOOL - LAB RENOVATION ROOMS 401, 406 & 407

ARCHITECT DELV Design 212 W 10th St, STE F125 Indianapolis, IN 46202 (317) 296-7400

MEP





No.	Description	Date
1	Addendum #01	05.13.2025

CLIENT PROJ. #: IU20241256 PROJECT #: 24-065 ISSUE DATE: 05/01/2025 DRW: MP | CHK: JR

MECHANICAL PIPING FOURTH FLOOR PLAN MP101

	IC	ENTITY DATA					FAN C		LE - 23 34			SOUND CR	ITERIA			EI		L DATA	
ARK	MANUFACTURE	R MODEL	SERV		IGHT BS) FAN			RFLOW (CFM)	ESP (IN-WG)	RPM	HP/BHP	SONES	DBA	UNI	T CONTROL		VOLT/PI	H/HZ	
EF-3	GREENHECK	VECKTOR-H-18-12	LAB/OI	FFICE	645 HIGH PLUN	ME EXHAUST	IRECT	2,500	2.00	1,689	3/1.78	23	73		VFD		460/3/0	60	1-2
Γ						SUPPLY AIR TE						. E							
ŀ		IDENTITY DAT	A			AIRFLOW D				E DATA			RE	HEAT C	OIL DATA				
	MARK	MANUFACTURER	MODEL	INLET DIAMETER	COOLING MAX (CFM)	HEATING MAX (CFM)	OCC. MIN (CFM)		I MAX (G) DISC			(EAT/LAT (°F)	APD (IN-WG)	FLOW (GPM)	EWT/LWT (°F)	WPD (FT-WG	ROWS	VALVE TYPE	
Ī	SAV-401	PRICE	SDV	10"	880	880	880	1.0		25	35,000	55 / 91.7	0.4	3.5	140 / 120	1.93	2	2-WAY	-
ſ	SAV-401A	PRICE	SDV	4"	150	150	75	1.0) 25	25	6,000	55 / 91.9	0.06	0.6	140 / 120	0.05	2	2-WAY	-
ſ	SAV-401B	PRICE	SDV	4"	150	150	75	1.0) 25	25	6,000	55 / 91.9	0.06	0.6	140 / 120	0.05	2	2-WAY	-
	SAV-401C	PRICE	SDV	4"	680	340	75	1.0) 25	25	6,000	55 / 91.9	0.06	0.6	140 / 120	0.05	2	2-WAY	-
	SAV-401D	PRICE	SDV	4"	260	225	75	1.0) 25	25	6,000	55 / 91.9	0.06	0.6	140 / 120	0.05	2	2-WAY	-
Ī	VAV-402	PRICE	SDV	6"	260	260	100	1.0) 25	25	10,000	55 / 90.4	0.16	1.0	140 / 120	0.12	2	2-WAY	-
	VAV-404	PRICE	SDV	6"	260	260	100	1.0) 25	25	10,000	55 / 90.4	0.16	1.0	140 / 120	0.12	2	2-WAY	-
	EX. CAV-406	PRICE	SDV	8"	420	420	420												

					EXHAUST F	AN SCHEDU	JLE - 23 34	4 23						
EI	NTITY DATA				F	AN DATA				SOUND C	RITERIA		ELECTRICAL DATA	4
R	MODEL	SERVICES	WEIGHT (LBS)	FAN TYPE	DRIVE TYPE	AIRFLOW (CFM)	ESP (IN-WG)	RPM	HP/BHP	SONES	DBA	UNIT CONTROL	VOLT/PH/HZ	NOTES
	VECKTOR-H-18-12	LAB/OFFICE	645	HIGH PLUME EXHAUST	DIRECT	2,500	2.00	1,689	3/1.78	23	73	VFD	460/3/60	1-2


			VARIA	ABLE VOLUME EXH	AUST TERMIN	AL BOX SCHEDUL	E				
		ID	ENTITY DATA		AIR	NOISE					
MARK	MANUFACTURER	MODEL	SERVICE	SPACE SERVED	INLET DIAMETER	MIN AIRFLOW (CFM)	MAX AIRFLOW (CFM)	SPI (IN-WG)	MAX DISCH.	MAX RAD.	
EAV-401	PRICE	LDV	GENERAL EXHAUST	LAB 401	10	200	800	1.00	25	25	-
HEV-401	SIEMENS	LGE	FUME HOOD EXHAUST	LAB 401 FUME HOOD	10	300	600	1.00	25	25	-
EAV-401A	PRICE	LDV	GENERAL EXHAUST	OFFICE 401A	4	125	200	1.00	25	25	-
EAV-401B	PRICE	LDV	GENERAL EXHAUST	PROCEDURE ROOM	4	125	200	1.00	25	25	-
EAV-401C	PRICE	LDV	GENERAL EXHAUST	PROCEDURE ROOM	4	125	200	1.00	25	25	-
EAV-401D	PRICE	LDV	GENERAL EXHAUST	OFFICE 401D	4	125	200	1.00	25	25	-
EAV-406	PRICE	LDV	GENERAL EXHAUST	LAB 406	8	420	420	1.00	25	25	-
				233	713 DIFFUSERS	, REGISTERS, AND GR					

	IDENTIT	Υ ΔΑΤΑ		NECK SIZE (IN)	MODUL	E SIZE	
MARK	DESCRIPTION	MANUFACTURER	MODEL	Ø	W	L	NOTES
EG24/12	LOUVER FACE GRILLE EXHAUST	PRICE	630		12"	24"	
LS24-10	LABSOX METAL-PAN DIFFUSER	DUCTSOX	DT200	10"	24"	24"	PROVIDE METAL BACK PAN WITH DIFFUSION PLATE. COLOR: SILVER
SPD24-6	SQUARE PLAQUE DIFFUSER	PRICE	SPD	6"	24"	24"	

EXHAUST FAN SCHEDULE NOTES:

1. DISCONNECT BY MANUFACTURER. PROVIDE AUXILLIARY CONTACT AT DISCONNECT TO DE-ENERGIZE OUTPUT POWER FROM VFD. 2. VFD FURNISHED BY MC, INSTALLED BY EC/CIC.

1



MODULATING FLOW CONTROL/ 2-WAY BALANCING T.C. VALVE VALVE (TYPICAL)

BALL VALVE WITH MEMORY STOP IN PIPING 2" AND SMALLER BUTTERFLY VALVE IN PIPING

ABOVE 2"

UNION (TYP.) -

MV

P/T PLUG (TYP.)




INDIANA UNIVERSITY

IU20241256 BL065 OPTOMETRY SCHOOL - LAB RENOVATION ROOMS 401, 406 & 407

ARCHITECT DELV Design 212 W 10th St, STE F125 Indianapolis, IN 46202 (317) 296-7400

MEP







No.	Description	Date
1	Addendum #01	05.13.2025


CLIENT PROJ. #: IU20241256 PROJECT #: 24-065 ISSUE DATE: 05/01/2025 DRW: MP | CHK: JR


SCHEDULES, DETAILS, AND DIAGRAMS

















TERMINAL BOX WITH REHEAT 2 (VAV-402,VAV-404) NOT TO SCALE




INDIANA UNIVERSITY

IU20241256 BL065 OPTOMETRY SCHOOL - LAB RENOVATION ROOMS 401, 406 & 407

ARCHITECT DELV Design 212 W 10th St, STE F125 Indianapolis, IN 46202 (317) 296-7400

MEP








No.	Description	Date
1	Addendum #01	05.13.2025


CLIENT PROJ. #: IU20241256 PROJECT #: 24-065 ISSUE DATE: 05/01/2025 DRW: MP | CHK: JR
















EXHAUST AIR TO CENTRAL

EXHAUST AIR

TO CENTRAL

EXHAUST SYSTEM A. GENERAL 1. CONTROL OF AIRFLOW TO AN FROM EACH LABORATORY SPACE AND CONTROL OF SPACE TEMPERATURE WITHIN THE LABORATORY SPACE SHALL BE ACCOMPLISHED BY THE LABORATORY AIRFLOW CONTROL SYSTEM (LACS). THE LACS SHALL UTILIZE DDC

B. AIRFLOW CONTROL

ANALOG INPUTS

SPACE TEMPERATURE (ZN-T)

AIR VALVE POSITION AS A PERCENT OPEN (DPR-O)

LABORATORY AIRFLOW SEQUENCE OF OPERATION

MICROPROCESSOR BASED LOGIC TO ACHEIVE ALL CONTROL FUNCTIONS.

TEMPERATURE CONTROL VALVE POSITION AS A PERCENT OPEN (RH-VLV)

SUPPLY AIRFLOW VALUE FOR SUPPLY TERMINAL UNITS (SA-CFM) DISCHARGE AIR TEMPERATURE FOR SUPPLY TERMINAL UNITS (DA-T)

REQUIRED AIRFOW FOR EACH FUMEHOOD WITH SASH CLOSED.

3. FUME HOOD EXHAUST VALVE AND CONTROLLER FURNISHED BY SIEMENS, INSTALLED BY CIC. 4. LABORATORY AIRFLOW CONTROL HARDWARE FURNISHED BY SIEMENS, 1INSTALLED BY CIC. $\overbrace{}$ 5. SUPPLY AIR TERMINAL UNIT FOR 406 IS EXISTING. REMOVE AND REPLACE EXISTING HYDRONIC CONTROL VALVE ACTUATOR. CONTROL VALVE BODY REMAINS. REUSE EXISTING DAMPER ACTUATOR. PROVIDE NEW SPACE SENSOR FOR TERMINAL BOX CONTROL. 6. LABORATORY FUME HOOD OPERATOR DISPLAY PANEL FURNISHED BY SIEMENS AND INSTALLED ON FACE OF FUME HOOD AND WIRED TO FUME HOOD CONTROLLER BY CIC.

2. OPERATE EXHAUST VALVE TO MAINTAIN REQUIRED DESIGN AIRFLOW RATE FOR EACH FUMEHOOD WITH SASH OPEN AND MINIMUM

2. FUME HOOD EXHAUST VALVE (HEV-401): MODULATE EXHAUST AIR VALVE TO MAINTAIN 80 FPM WHEN LABORATORY IS OCCUPIED.

3. GENERAL EXHAUST VALVE (EAV-401): MODULATE GENERAL EXHAUST TERMINAL UNIT DAMPER TO MAINTAIN TOTAL EXHAUST AIRFLOW (FUME HOODS, & GENERAL EXHAUST VALVE) AT 6 AC/HR CONTINUOUSLY (24/7). GENERAL EXHAUST IS THE DIFFERENCE BETWEEN THE

TOTAL REQUIRED EXHAUST AIRFLOW FOR THE SPACE AND THE EXHAUST AIRFLOW FROM FUME HOOD AND IN THE LABORATORY SPACE.

AIRFLOW. MODULATE HEATING COIL TEMPERATURE CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE SETPOINT.

GRAPHICALLY DISPLAY THE FOLLOWING POINTS, AT A MINIMUM, AT THE OPERATOR WORKSTATION:

EXHAUST AIRFLOW VALUE FOR EXHAUST VALVES AND EXHAUST TERMINAL UNITS (EXH-CFM)

1. SUPPLY AIR TERMINAL UNIT WITH REHEAT (SAV-401): MODULATE SUPPLY TERMINAL UNIT DAMPER TO MAINTAIN OFFSET WITH EXHAUST

1. CONTROL VALVE AND ACTUATOR FURNISHED BY SIEMENS, INSTALLED BY


2. TERMINAL UNIT CONTROLLER FURNISHED BY SIEMENS, INSTALLED BY CIC.

401B, **401C**, **401D**, **AND 406** NOT TO SCALE

AIRFLOW DIAGRAM NOTES:

MC/CIC.

LABORATORY AIRFLOW DIAGRAM- 401A,



EXHAUST AIR

1. SUPPLY AIR TERMINAL UNIT WITH REHEAT (SAV-XXX): MODULATE SUPPLY TERMINAL UNIT DAMPER TO MAINTAIN OFFSET WITH EXHAUST AIRFLOW. MODULATE HEATING COIL TEMPERATURE CONTROL VALVE TO MAINTAIN SPACE TEMPERATURE SETPOINT. 2. EXHAUST VALVE (EAV-XXX): MODULATE EXHAUST AIR VALVE TO MAINTAIN MAXIMUM EXHAUST WHEN LABORATORY IS OCCUPIED.

GRAPHICALLY DISPLAY THE FOLLOWING POINTS, AT A MINIMUM, AT THE OPERATOR WORKSTATION:

EXHAUST AIRFLOW VALUE FOR EXHAUST VALVES AND EXHAUST TERMINAL UNITS (EXH-CFM)

B. AIRFLOW CONTROL

ANALOG INPUTS

SPACE TEMPERATURE (ZN-T)

AIR VALVE POSITION AS A PERCENT OPEN (DPR-O)

TEMPERATURE CONTROL VALVE POSITION AS A PERCENT OPEN (RH-VLV)

SUPPLY AIRFLOW VALUE FOR SUPPLY TERMINAL UNITS (SA-CFM)

DISCHARGE AIR TEMPERATURE FOR SUPPLY TERMINAL UNITS (DA-T)

1. CONTROL OF AIRFLOW TO AN FROM EACH LABORATORY SPACE AND CONTROL OF SPACE TERMPERATURE WITHIN THE LABORATORY SPACE SHALL BE ACCOMPLISHED BY THE LABORATORY AIRFLOW CONTROL SYSTEM (LACS). THE LACS SHALL UTILIZE DDC MICROPROCESSOR BASED LOGIC TO ACHEIVE ALL CONTROL FUNCTIONS.

A. GENERAL

LABORATORY AIRFLOW SEQUENCE OF OPERATION




INDIANA UNIVERSITY

IU20241256 BL065 **OPTOMETRY SCHOOL** - LAB RENOVATION ROOMS 401, 406 & 407

ARCHITECT DELV Design 212 W 10th St, STE F125 Indianapolis, IN 46202 (317) 296-7400

MEP





No.	Description	Date
1	Addendum #01	05.13.2025

CLIENT PROJ. #: IU20241256 PROJECT #: 24-065 ISSUE DATE: 05/01/2025 DRW: MP | CHK: JR

