



**20230515 – BL001 – Lowell E. Baier Hall – Replace Generator to Exterior
Addendum 2**

May 11, 2026

General Notifications

Modifications described herein shall be incorporated into the project documents. All other work described in the project documents shall remain unchanged.

Acknowledge receipt of this Addendum by noting it on the Bid Form. Failure to do so may subject bidder to disqualification. This Addendum is a part of the contract documents.

Bidding Questions and Answers

Question 1: In reference to Spec Section 044313.2.1.4, is honed finish for the cut stone cap only? Berkshire Ashlar is a split face product and will be provided as such.

Answer 1: Yes, honed finish on the cut stone cap and split face is acceptable on the cut stone wall.

Question 2: In reference to Specification 044313.2.5.D, Berkshire is provided in random lengths and cut to fit in the field. Corners are also dressed in the field for the split face appearance. Please confirm if this is acceptable.

Answer 2: Yes, this is acceptable.

Question 3: In reference to Specification 044313.2.5.E, Please confirm sawn backs are required. Typically, Berkshire Ashlar is rough back.

Answer 3: Sawn back is required to maintain proper air gap and to maintain a uniform thickness to the wall.

Question 4: Are six 4" conduits required for the ductbank?

Answer 4: Yes.

Changes to the Specifications

Stone Masonry Veneer Spec Section 044313.2.1.6: Add "c. TexaCon Cut Stone" as an approved equal.

Stone Masonry Veneer Spec Section 044313.2.1.6: Add "d. Limestone Fabricators" as an approved equal.

Notice To Bidders:

Revise to read bid date to read, "2:00pm Eastern Time, on Thursday May 21, 2026."

End of ADDENDUM 2