IU BL573 Smith Research Center – HVAC Building Fresh Air
IU #20192459

ADDENDUM #2

October 30, 2020

General Notifications

Modifications described herein shall be incorporated into the project documents. All other work described in the project documents shall remain unchanged.
Acknowledge receipt of this Addendum by noting it on the Bid Form. Failure to do so may subject bidder to disqualification. This Addendum is a part of the contract documents.

Changes to the Drawings

1. Sheet E801 – ELECTRICAL DETAILS AND SCHEDULES – BASE BID
    a. Add card reader installation detail – see attached sheet.
2. Sheet H701 – HVAC SYSTEM DIAGRAMS
    a. Add the following notes for the heating hot water diagram:
        i. Install water meter in makeup water line equal to Badger Meter Recordall Disc Series, ¾" size. CIC shall wire water meter to temperature control panel; coordinate landing location with Siemens.
    b. Add the following for both the chilled water and heating hot water diagrams:
        i. Chemical treatment shall be by Weas Engineering (Dale Scherschel; dale.scherschel@weasengineering.com). Chilled water and heating hot water piping systems shall be chemically cleaned, flushed, and passivated prior to startup. Coordinate procedure with Weas Engineering and submit report to engineer after system treatment is complete.
        ii. Install a pressure gauge on inlet and outlet of filter feeder.
        iii. Install ½" sample port on inlet side of filter feeder.
        iv. Install corrosion coupon rack on inlet side of filter feeder – coordinate requirements with Weas Engineering.

Changes to the Specifications

1. Section 232223 – STEAM CONDENSATE PUMPS
    a. Add Shipco as an approved manufacturer.

2. Section 233300 – AIR DUCT ACCESSORIES
    a. Add POTTORFF & NCA as approved manufacturers for 2.3 Backdraft Dampers, 2.4 Volume Dampers, and 2.5 Fire Dampers.

Attachments

1. Sheet E801

End of Addendum #2