

ADDENDUM NO.3 – November 9, 2020

**Indiana University Northwest
NW818 - Marram Hall -
Classrooms/Corridors/Lab Renovations
Gary, Indiana
IU: 20200266**

This Addendum, issued prior to bidding, alters, amends, corrects, or clarifies the Construction Bid Documents to the extent stated herein and does thereby become a part of the Construction Bid Documents, and will become part of the Contract Documents of the successful bidder. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

ADDENDUM #3

QUESTIONS AND ANSWERS

1. At A9, delete answer as written in its entirety, and replace with the following Answer:

A9: Refer to General Ceiling Notes #8, ...“Adjust grid layout as required to accommodate existing sprinkler heads. However, grid lines shall be installed straight & aligned for the entire width or length of the room or space. Do not jog or off-set individual T’s.” For the corridors, where the existing sprinkler heads are dead center in the existing 2x4 tiles, off-set the entire middle grid line +/- 2 inches as needed and cut 2x4 tiles to fit on either side of the grid line.

END OF ADDENDUM